

VAN NOSTRAND'S SCIENCE SERIES.

No. 38.

Price 50 Cts.

A HAND-BOOK

OF THE

ELECTRO-MAGNETIC

TELEGRAPH

BY

A. E. LORING,

PRACTICAL TELEGRAPHER



FOURTH EDITION REVISED.

NEW YORK:

J. VAN NOSTRAND COMPANY.

23 NASSAU ST. AND 27 WARREN STREET.

1900

TK
5263
.L8
1900

THE

LIBRARY OF CONGRESS.

S.

Am.

Chap. Copyright No.

Shelf TK526

No. 1.

UNITED STATES OF AMERICA.

No. 2.

Ed.
d.x
E.
rn.

- No. 3.—PRACTICAL DESIGNING OF RETAINING-WALLS. By Arthur Jacob, A.B. Second edition, revised, with additions by Prof. W. Cain.
- No. 4.—PROPORTIONS OF PINS USED IN BRIDGES. By Chas. E. Bender, C.E. 2d edition, with appendix.
- No. 5.—VENTILATION OF BUILDINGS. By W. F. Butler. Second edition, re-edited and enlarged by James L. Greenleaf, C. E.
- No. 6.—ON THE DESIGNING AND CONSTRUCTION OF STORAGE RESERVOIRS. By Arthur Jacob, A. B. Second edition, revised, with additions by E. Sherman Gould.
- No. 7.—SURCHARGED AND DIFFERENT FORMS OF RETAINING-WALLS. By James S. Tate, C.E.
- No. 8.—A TREATISE ON THE COMPOUND ENGINE. By John Turbull, jun. Second edition, revised by Prof. S. W. Robinson.
- No. 9.—A TREATISE ON FUEL. By Arthur V. Abbott, C.E. Founded on the original treatise of C. William Siemens, D.C.L.
- No. 10.—COMPOUND ENGINES. Translated from the French of A. Mallet. Second edition, revised, with results of American Practice by Richard H. Buel, C.E.
- No. 11.—THEORY OF ARCHES. By Prof. W. Allan.
- No. 12.—THEORY OF VOUSOIR ARCHES. By Prof. W. Cain. Second edition, revised and enlarged.
- No. 13.—GASES MET WITH IN COAL-MINES. By J. J. Atkinson. Third edition, revised and enlarged by Edward H. Williams, jun.
- No. 14.—FRICTION OF AIR IN MINES. By J. J. Atkinson. Second American edition.
- No. 15.—SKEW ARCHES. By Prof. E. W. Hyde, C.E. Illustr.
- No. 16.—A GRAPHIC METHOD FOR SOLVING CERTAIN ALGEBRAIC EQUATIONS. By Prof. G. L. Vose.
- No. 17.—WATER AND WATER-SUPPLY. By Prof. W. H. Corfield of the University College, London. Second American edition.
- No. 18.—SEWERAGE AND SEWAGE PURIFICATION. By M. N. Baker, Associate Editor "Engineering News."

THE VAN NOSTRAND SCIENCE SERIES.

- No. 19.—STRENGTH OF BEAMS UNDER TRANSVERSE LOADS. By Prof. W. Allan, author of "Theory of Arches." Second edition, revised.
- No. 20.—BRIDGE AND TUNNEL CENTRES. By John B. McMaster, C.E. Second edition.
- No. 21.—SAFETY VALVES. Second Edition. By Richard H. Buel, C.E.
- No. 22.—HIGH MASONRY DAMS. By E. Sherman Gould, M. Am. Soc. C. E.
- No. 23.—THE FATIGUE OF METALS UNDER REPEATED STRAINS. With various Tables of Results and Experiments. From the German of Prof. Ludwig Spangenburg, with a Preface by S. H. Shreve, A.M.
- No. 24.—A PRACTICAL TREATISE ON THE TEETH OF WHEELS. By Prof. S. W. Robinson. Second edition, revised.
- No. 25.—ON THE THEORY AND CALCULATION OF CONTINUOUS BRIDGES. By Mansfield Merriman, Ph.D.
- No. 26.—PRACTICAL TREATISE ON THE PROPERTIES OF CONTINUOUS BRIDGES. By Charles Bender, C.E.
- No. 27.—ON BOILER INCRUSTATION AND CORROSION. By F. J. Rowan. New Ed. Rev. by F. E. Idell.
- No. 28.—TRANSMISSION OF POWER BY WIRE ROPES. Second edition. By Albert W. Stahl, U.S.N.
- No. 29.—STEAM INJECTORS. Translated from the French of M. Leon Pochet.
- No. 30.—TERRESTRIAL MAGNETISM AND THE MAGNETISM OF IRON VESSELS. By Prof. Fairman Rogers.
- No. 31.—THE SANITARY CONDITION OF DWELLING-HOUSES IN TOWN AND COUNTRY. By George E. Waring, jun.
- No. 32.—CABLE-MAKING FOR SUSPENSION BRIDGES. By W. Hildebrand, C.E.
- No. 33.—MECHANICS OF VENTILATION. By George W. Rafter, C.E. New and Revised Edition.
- No. 34.—FOUNDATIONS. By Prof. Jules Gaudard, C.E. Second edition. Translated from the French.
- No. 35.—THE ANEROID BAROMETER: ITS CONSTRUCTION AND USE. Compiled by George W. Plympton. Fourth edition.
- No. 36.—MATTER AND MOTION. By J. Clerk Maxwell, M.A. Second American edition.
- No. 37.—GEOGRAPHICAL SURVEYING; ITS USES, METHODS, AND RESULTS. By Frank De Yeaux Carpenter, C.E.
- No. 38.—MAXIMUM STRESSES IN FRAMED BRIDGES. By Prof. William Cain, A.M., C.E. New and revised edition.

THE VAN NOSTRAND SCIENCE SERIES.

- No. 39.—A HANDBOOK OF THE ELECTRO-MAGNETIC TELEGRAPH. By A. E. Loring.
- No. 40.—TRANSMISSION OF POWER BY COMPRESSED AIR. By Robert Zahner, M.E. Second edition.
- No. 41.—STRENGTH OF MATERIALS. By William Kent, C.E., Assoc. Editor, *Engineering News*. Second Ed.
- No. 42.—VOUSSOIR ARCHES APPLIED TO STONE BRIDGES, TUNNELS, CULVERTS, AND DOMES. By Prof. William Cain.
- No. 43.—WAVE AND VORTEX MOTION. By Dr. Thomas Craig, of Johns Hopkins University.
- No. 44.—TURBINE WHEELS. By Prof. W. P. Trowbridge, Columbia College. Second edition. Revised.
- No. 45.—THERMODYNAMICS. By Prof. H. T. Eddy, University of Cincinnati.
- No. 46.—ICE-MAKING MACHINES. From the French of M. Le Doux. Revised by Prof. Denton.
- No. 47.—LINKAGES; THE DIFFERENT FORMS AND USES OF ARTICULATED LINKS. By J. D. C. de Roos.
- No. 48.—THEORY OF SOLID AND BRACED ARCHES. By William Cain, C.E.
- No. 49.—ON THE MOTION OF A SOLID IN A FLUID. By Thomas Craig, Ph.D.
- No. 50.—DWELLING-HOUSES: THEIR SANITARY CONSTRUCTION AND ARRANGEMENTS. By Prof. W. H. Corfield.
- No. 51.—THE TELESCOPE: ITS CONSTRUCTION, ETC. By Thomas Nolan.
- No. 52.—IMAGINARY QUANTITIES. Translated from the French of M. Argand. By Prof. Hardy.
- No. 53.—INDUCTION COILS: HOW MADE AND HOW USED. Fifth edition.
- No. 54.—KINEMATICS OF MACHINERY. By Prof. Kennedy. With an introduction by Prof. R. H. Thurston.
- No. 55.—SEWER GASES: THEIR NATURE AND ORIGIN. By A. de Varona. 2d ed., revised and enlarged.
- No. 56.—THE ACTUAL LATERAL PRESSURE OF EARTH-WORK. By Benjamin Baker, M. Inst. C.E.
- No. 57.—INCANDESCENT ELECTRIC LIGHTING. A Practical Description of the Edison System. By L. H. Latimer, to which is added the Design and Operation of Incandescent Stations. By C. J. Field, and the Maximum Efficiency of Incandescent Lamps, by John W. Howell.
- No. 58.—THE VENTILATION OF COAL-MINES. By W. Fairley, M.E., F.S.S., and Geo. J. André.
- No. 59.—RAILROAD ECONOMICS; OR, NOTES WITH COMMENTS. By S. W. Robinson C.E.

A HAND-BOOK
OF THE
ELECTRO-MAGNETIC
TELEGRAPH

BY
A. E. LORING,
A PRACTICAL TELEGRAPHER.



FOURTH EDITION REVISED.

NEW YORK:
D. VAN NOSTRAND COMPANY.
23 MURRAY AND 27 WARREN STREET.
1900.

11718

Library of Congress

TWO COPIES RECEIVED

JUN 28 1900

Copyright entry

June 4, 1900

No. *As 13845*

SECOND COPY.

Delivered to

ORDER DIVISION,

JUN 29 1900

*TK 3262
L
no*

COPYRIGHT, 1878, BY D. VAN NOSTRAND.

COPYRIGHT, 1900, BY D. VAN NOSTRAND COMPANY.

64442

TH 322

L 57



O-4069

INTRODUCTION.

It has been the aim of the author in the preparation of this little book, to present the principles of the Electro-Magnetic Telegraph, in a brief, concise manner, for the benefit of practical operators and students of telegraphy. The works on telegraphy which have thus far been presented, besides being expensive, have contained much that is useless, or which is not in a form to be readily understood by young and inexperienced telegraphers. Although this little work must be acknowledged incomplete, it is hoped that it may go far toward supplying the deficiency which has existed ; or, at least, serve as a stepping-stone to the study of the more complete works on electricity and telegraphy.

THE AUTHOR.

PREFACE TO FOURTH EDITION.

In the present edition, an attempt has been made to revise the original text, as the present state of telegraph practice requires, without increasing the size of the book. A new chapter, describing in outline the duplex and quadruplex methods of telegraphy has been added, however, which it is believed will materially increase the value of the work.

A. E. L.

January 5th, 1900.

CONTENTS.

PART I.—ELECTRICITY AND MAGNETISM.

	PAGE
Electricity—Positive and Negative.....	9
Conductors and Non-Conductors.....	10
Galvanic Batteries.....	11
Galvanic Circuits.....	12
Electrical Quantity and Intensity.....	13
Gravity Batteries.....	15
Resistance.....	17
Electro-Motive Force.....	17
Ohms Law.....	18
Measurement of Currents.....	20
Measurement of Resistance.....	20
Divided Circuits.....	21
Electro-Magnets.....	23
Differential Magnets.....	25
Magnetic Induction.....	26
Residual Magnetism.....	27
Proportion of Electro-Magnets to Circuit..	27

PART II.—THE MORSE TELEGRAPH.

Fundamental Principle.....	28
Telegraph Circuits.....	29
Intermediate Offices.....	32

	PAGE
The Local Circuit.....	33
Ground Wires.....	35
The Key.....	35
The Relay.....	38
The Sounder.....	40
Main Line Sounders.....	41
The Box Relay.....	43
Cut-Outs and Other Switches.....	45
Lightning Arresters.....	48
The Switch Board.....	50
Loops.....	54
Arrangement of Offices.....	54
Arrangement of Batteries.....	55
Repeaters.....	56
Automatic Repeaters.....	59

PART III.—THE QUADRUPLIX.

Duplex and Quadruplex Systems.....	62
The Stearns Duplex.....	63
The Condenser.....	68
The Polar Duplex.....	70
The Quadruplex.....	75

PART IV.—PRACTICAL TELEGRAPHY.

Alphabet and Numerals.....	83
Adjustment of Instruments.....	84
Testing Telegraph Lines.....	86
Breaks.....	86

CONTENTS.

vii

	PAGE
Escapes	88
Grounds.....	90
Crosses	90
Maintenance of Battery.....	91
Balancing the Quadruplex.....	93

PART V.—CONSTRUCTION OF LINES.

The Conductors.....	95
The Insulators.....	97
Fitting up Offices.....	98
Ground Wire Connections.....	99
Private and Short Lines.....	100

APPENDIX.

Suggestions and Exercises for Learners....	104
Index	111

ELECTRO-MAGNETIC TELEGRAPH.

ELECTRICITY AND MAGNETISM.

ELECTRICITY.—POSITIVE AND NEGATIVE.

THE real nature of electricity is unknown. It is often spoken of as a *fluid*, and is said to *flow* in a *current*, but these terms may be considered as used more for the sake of convenience, than as indicating the real nature of electricity.

There are two kinds of electricity, or it exists in two different states, known as *positive* and *negative*; and experiment shows, that whenever one kind is developed that of the opposite kind is always developed in an exactly equal quantity. These two kinds of electricity are usually designated by the signs + and —. It is a law of electricity, that *electricities of like sign*

repel each other, and electricities of unlike sign attract each other.

CONDUCTORS AND NON-CONDUCTORS.

Electricity passes through some substances easily, and through others with difficulty, or scarcely at all. The first class of substances are called *conductors*, the second *non-conductors*, or *insulators*. No absolute division can be made between conductors and non-conductors, as the property of conduction exists in every conceivable degree, from the best conductor to the best insulator, or *worst conductor*. In the following list the first named substance is the best conductor, and the last named the best insulator.

CONDUCTORS.

Silver,
Copper,
Gold,
Zinc,
Platinum,
Iron,
Tin,
Lead,
Mercury,
Acids,
Water,


NON-CONDUCTORS.

Dry wood,
Porcelain,
Dry Paper,
Silk,
Glass,
Gutta Percha,
India Rubber,
Shellac,
Hard Rubber
Paraffine,
Dry Air.

GALVANIC BATTERIES.

Galvanic, or Voltaic electricity is developed by chemical action. When two plates of metal, of different kinds, as copper and zinc, for example, are immersed in a cup containing an acid, and are con-

Fig. 1.



Galvanic Element.

nected by wires at the top, as represented in Fig. 1, a current of electricity will flow from the copper to the zinc through the wires, and from the zinc to the copper through the acid. If the wires connecting the two metals are separated, the cur-

rent of electricity instantly ceases, but starts again whenever the wires are connected. An apparatus for generating electricity in this way is called a *galvanic battery*. The copper slip is called the positive (+) *pole* of the battery, and the zinc the negative (—) *pole*. The principal kinds of batteries used in operating the telegraph will be described hereafter.

GALVANIC CIRCUITS.

The path traversed by the current of a battery is called a *circuit*. The circuit of the battery shown in Fig. 1 consists of the metals, wires, and the acid through which the current of electricity passes. It is a law of the electric current that *there must be a continuous, unbroken circuit, by which the current may pass entirely around from one pole of the battery to the other, or no current will start from the battery*. The smallest break in the circuit is sufficient to interrupt the current instantly, but it begins to flow again the instant the circuit is again completed. The direction of the current through the

circuit is always from the positive to the negative pole of the battery.

It may be more correct, however, considering the electrical force as a *current*, to say that there are two currents flowing in opposite directions, and for convenience the positive one only is spoken of as the current.

ELECTRICAL QUANTITY AND INTENSITY.


A battery may consist of a single cup, or cell, or of an indefinite number of cups connected together by wires. In connecting them together, the copper, or positive pole of the first cup must be connected by a wire with the negative pole of the second, and the positive pole of the second with the negative of the third, and so on throughout the series, always connecting unlike or opposite poles, because, according to the law of attraction and repulsion already stated, *poles of like sign oppose one another, and poles of unlike sign attract one another.*

The *quantity* of electricity generated by three cells of battery connected as

directed above, is no greater than that generated by one cell, but the *intensity* of the current generated will increase in proportion to the number of cells so connected. Intensity or *tension* is the force which enables the current to push its way through a conductor, or to overcome resistance.

If two or more cells of battery are connected as shown in Fig. 2, with all the

Fig. 2.



Galvanic Battery—Quantity Arrangement.

positive poles connected to one end of the wire conductor, and all the negative poles connected to the other end, the *quantity* of the current generated will be in proportion to the number of cells, but the

intensity of the current will be no greater than that of a single cell.


The general principle is, that quantity increases with the surface of metal connected with each pole, whether that surface is all in one cell, or distributed through several cells connected as in Fig. 2. The intensity increases with the number of elements, or cells, having opposite poles connected, and does not depend upon the size of the metals used. Consequently, large cells evolve a greater quantity of current than small ones, but of no greater tension.

GRAVITY BATTERIES.

The various forms of battery formerly used in operating the telegraph have been entirely superseded by the *gravity battery*. There are a variety of forms, without any material difference in the principle involved. That shown in Fig. 2a is the "crowfoot" battery, so called from the peculiar shape of the zinc. The copper is placed at the bottom of the jar, the zinc at the top. The sul-

phate of copper solution at the bottom of the jar and the sulphate of zinc solu-

Fig. 2a.



Gravity Battery.

tion at the top are kept separate by the difference in their specific gravities.

RESISTANCE.

Resistance is the opposition which the conductor, or circuit offers to the passage of the current. Thus the best conductor offers the least resistance, and the poorest conductor the greatest resistance. Resistance may be considered as the reciprocal of conduction. Resistance is measured by *Ohms*.

In the case of two conducting wires of the same material, that which presents the largest area of cross-section to the current offers the least resistance. Thus, although copper is a better conductor than iron, an iron wire of large size may have a lower resistance than a copper wire of smaller size. The conducting power of a wire increases, and its resistance decreases, in proportion as the area of its section increases. On the other hand, the resistance of a conducting wire of a given material increases in proportion to its length.

ELECTRO-MOTIVE FORCE.

The power which a cell of battery possesses of causing the transfer of its

current from one place to another is its *electro-motive force*. In other words, the electro-motive force of a current is its power of overcoming resistance—its energy. Electro-motive force may be defined as tension in a state of motion; and tension, as electro-motive force in a state of rest. (*Haskin's Galvanometer.*)

Electro-motive force, or potential, is measured by the unit called the *Volt*.

OHM'S LAW.

The amount of the current which will pass through a circuit depends, first, upon the resistance which the circuit offers to the passage of the current, and second, upon the intensity of the electro-motive force which tends to overcome that resistance. The amount of the current may be found, according to *Ohm's law*, which may be stated thus:

E represents the electro-motive force,
R the resistance, and

C the current which will pass through the circuit, thus:

$$C = \frac{E}{R}$$

Fig. 3.



Galvanometer.

or, *the current is equal to the electro-motive force divided by the resistance.*

MEASUREMENT OF CURRENTS.

Electric currents may be measured by an instrument called a *galvanometer*, one form of which is shown in Fig. 3. It consists of a magnetic needle surrounded by a coil of insulated wire. When a current is passed through the coil of wire, its amount is marked by the deflection of the needle on the face of a dial, the degree of deflection being always in proportion to the strength of the current. The strength of the current is measured by a unit called the *ampere*.

MEASUREMENT OF RESISTANCE.

The resistance of a conductor may be measured by an instrument called a *rheostat* (Fig. 4), used in connection with a galvanometer. The rheostat consists essentially of resistance coils of fine German silver wire inclosed in a box. Binding posts are provided for placing it in circuit, and any desired number of the


coils may be cut out by inserting brass plugs in the top of the box, according to the resistance required.

The rheostat and galvanometer are put in circuit with the conductor whose resistance is to be measured, and the deflection of the needle of the galvanometer is noted. The conductor to be measured is then taken out of the circuit, and as much resistance is thrown in by the rheostat as will give the same deflection of the needle. The resistance marked by the rheostat will, evidently, be equal to that of the conductor previously in circuit.

DIVIDED CIRCUITS.

When two or more wires are connected together so as to form one continuous wire, the resistance of the whole circuit will be the sum of the resistances of the wires which compose it. But if two or more wires are arranged side by side, the ends being connected with each other, the current is divided among the several conductors, and the conducting power

Fig. 4.



Rheostat.

Handwritten notes:
Circuit
Diagram
See
Page 23

of the whole is equal to the sum of the conducting power of the wires which compose it.


When a current of a given electro-motive force divides between two or more branches of the conductor, the strength of the current in each branch is, by Ohm's law, inversely proportional to the resistance. An important application of this principle occurs in the duplex and quadruplex systems of telegraphy, where the current is caused to divide equally between two branches of the conductor, —one consisting of the line and the other of a rheostat circuit adjusted to equal the resistance of the line.

ELECTRO-MAGNETS. .

A simple form of electro-magnet is shown in Fig. 5. A conducting wire, insulated by being covered with silk or cotton, so that the current must traverse its entire length, is wound several times around each arm of a U shaped piece of soft iron. When a current of electricity is passed through the insulated conduct-

ing wire, the soft iron U instantly becomes magnetized, and attracts an iron

Fig. 5.




Simple Electro-Magnet.

bar, A, called an *armature*, which is placed near its ends or *poles*. As soon as the current of electricity ceases to pass through the wire, the soft iron U is demagnetized and ceases to attract its armature.

Electro-magnets for use in telegraphy are made as represented in Fig. 6. Two spools, *a b*, having soft iron cores, are wound with fine silk-insulated copper wire, as thread is wound upon a spool.

The two spools are fixed upon a bar of iron, B, called a *yoke*. A is the arma-

Fig. 6.



Electro-Magnet.

ture which is attracted toward the cores or poles, *e e*, whenever the current passes through the coils of the magnet.

DIFFERENTIAL MAGNETS.

It will be observed that the wire passes around the soft iron U, Fig. 5, in such a direction that if the U is straightened out the convolutions will all lie in one direction. One end of the bar becomes the north pole and the other the south pole of the magnet, and the polarity may

be reversed by changing the direction of the current around the bar. This may be by either changing the direction of the coils, or by reversing the poles of the battery.

A differential electro-magnet may be made by passing two separate coils around the core, and its polarity is established according to the direction of the current. If currents of equal strength traverse the two coils in opposite directions they tend to establish opposite polarities and the magnetic effect is neutralized.

MAGNETIC INDUCTION.

When either pole of a magnet is placed near any object capable of magnetization, it is attracted toward the magnet, the magnet pole nearest the object developing magnetism of the opposite polarity by induction, and the two mutually attract each other. Thus each pole of an electro-magnet develops magnetism of an opposite polarity, by induction, in that end of the armature nearest to it, and the armature is attracted toward the electro-magnet.

RESIDUAL MAGNETISM.

When the current which passes through the coils of an electro-magnet is interrupted, demagnetization of the soft iron cores takes place. If the iron is very soft and pure this is effected almost instantly on the cessation of the current through the coils. But if the demagnetization is not complete, and a small amount of magnetism remains in the cores after the cessation of the current, it is called *residual magnetism*. A spring is therefore attached to the armature of the magnet, which overcomes the attraction of the residual magnetism, and draws the armature away from the poles of the magnet.

PROPORTION OF ELECTRO-MAGNETS TO THE CIRCUIT.

It is a law of the electric circuit, that *the maximum magnetic force is developed when the resistance of the coils of the electro-magnets in circuit is equal to the resistance of the other parts of the circuit; i. e., the conducting wires and battery.*

An electro-magnet is of the best proportions when the total thickness of the coils, measured from the outside to the core, is equal to the diameter of the core. When, therefore, the coils must be of high resistance, they are wound with a great length of *fine* wire. When the resistance of the circuit is light, a shorter length of coarser wire is used.

PART II.—THE MORSE TELEGRAPH.

FUNDAMENTAL PRINCIPLE.

THE Morse telegraph system is so called from the name of its inventor, Samuel F. B. Morse, an American, who constructed the first line between Baltimore and Washington in the year 1844.


Morse's telegraph operates upon the principle, that an electro-magnet may be alternately magnetized and demagnetized by stopping and starting a current of electricity, by opening and closing the circuit of which the electro-magnet forms a part.

TELEGRAPH CIRCUITS.

Fig. 7 represents a telegraph circuit, consisting of a line wire stretching from the station A to the station B; a battery T, an electro-magnet M, and a key K, for opening and closing the circuit, at each of the stations. To avoid the expense of a second wire to complete the circuit between the two stations, the line wire, after passing through the magnet, key and battery at each end of the line, is run to the ground at G, completing the circuit through the earth. Besides being less expensive, this plan has the additional advantage that the resistance of the circuit completed through the earth is less than it would be through a return wire, as the resistance of the earth is practically nothing. On very short lines sometimes a second wire is used, which constitutes what is called a *metallic* circuit.

When the circuit is closed at A by means of the key, K, the current traverses the circuit, passing through both electro-magnets, M M. causing them to attract

Fig. 7.



Telegraph Circuit.

their armatures as long as the current continues. When the circuit is again opened by the key, the current is interrupted, and the electro-magnets release their armatures. The effect is the same whether the circuit is opened and closed by the key at A, or at B. The effect, also, upon the electro-magnet is the same whether the key is at the same station with the magnet, or at another station many miles distant.

By the original method of operating the telegraph, the armature of the magnet at each station was attached to one end of a lever having a sharp pointed steel style in the other end, which indented a strip of paper drawn before it by means of clockwork. If the armature was attracted but an instant, the style came in contact with the paper only an instant, and indented it with a short mark, or *dot*. If the armature was attracted for a longer time, the result was a longer mark, or *dash* upon the paper. Thus, it will be observed, dots and dashes may be marked upon the paper by closing the circuit by

the key for a shorter or a longer time. If different combinations of dots and dashes are used to represent letters, it is evident that a message may be transmitted by means of the key at one station to the electro-magnet at another.

In more recent practice, the method of marking the signs upon paper has been superseded by arranging the lever attached to the armature in such a way that it will give sounds at shorter or longer intervals according to the time the circuit is closed. These intervals between sounds may be considered as representing dots and dashes, and for convenience the terms dot and dash are retained.

INTERMEDIATE OFFICES.


An indefinite number of intermediate or way stations may be introduced in the circuit between the two terminal stations of the line, each station or office being provided with its key and magnet. The circuit may be opened by a key placed at one of these intermediate stations, at any point on the line, and the effect upon

every magnet in the circuit will be precisely the same; but it is obvious that only one key can be operated for opening and closing the circuit at the same time.

THE LOCAL CIRCUIT.

On a circuit as long as a telegraph line reaching from city to city, the resistance of the long line of wire is so great that the current is often weakened to such an extent in passing over it, that sufficient magnetic force is not developed in the electro-magnets to attract their armatures with the power necessary to mark paper, or give a satisfactory sound to the motions of a lever. For this reason, instead of placing the magnet of the recording or sounding instrument in the *main* circuit, its place is supplied by a *relay* magnet, M, (Fig. 8). The armature of the relay magnet is attached to a lever, S, which opens and closes the circuit of another battery, B, at the point P. This second or *local* circuit is represented by the dotted lines. When the *main* circuit, or line is closed, the relay magnet attracts its

armature and closes the *local* circuit, in which is placed the recording or sounder



magnet G. The lever of the relay magnet is so light that a weak current is sufficient to work it, but the resistance of the local circuit, which is composed of only a few feet of wire, is so small that

nearly the entire force of the local battery is effective upon the local magnet. It will be noticed that although the local circuit depends for its action upon the main circuit, the main circuit is entirely separate and independent from the local, and is not affected in the least by its action.

GROUND WIRES.


At every intermediate station, a wire called a *ground wire* is run from the office to the ground. This wire may be connected with the line wire so as to divide the main circuit into two distinct and independent circuits. The uses of the ground wire will be explained more fully hereafter.

THE KEY.

The key, or sending instrument is represented in Fig. 9. It consists of a lever of brass, L, about five inches long, which is hung on a shaft between two set screws on the frame or base B. The key is fastened to the operating table by two legs, R R', which pass through the table and

are secured by nuts underneath. The circuit is formed through the key by cutting the wire of the main circuit and con-

Fig. 9.



Key.

necting one of the ends to each of the legs. The leg, R' , is in direct connection with the brass base of the instrument, but the other leg, R , is insulated from it by being set in a piece of hard rubber, so that the circuit is broken at this point and

the current cannot pass from R' to R. The leg, R, terminates in a *platinum point*, P, and a similar platinum point, P, is placed in the lever L.

When it is desired to complete the circuit, the lever is pressed down by the pressure of the fingers upon a hard rubber finger piece, F, bringing the two platinum points, P P, in contact, and completing the connection between R' and R through the lever and platinum points. When the pressure upon F is released, a spring under the lever restores it to its former position, separating the platinum points, and the circuit is broken.


C is a *circuit closer*, which completes the connection and closes the circuit permanently when it is pushed against the anvil which forms the top of the leg, R. This is always done when the key is not in use, for if the circuit through it was not completed in this way, the current could not flow through the circuit, and all the other keys situated in it would be useless. The play of the lever, or the

distance between the platinum points is regulated by a set screw, D, in the end of the lever. Sometimes another set screw, S, is provided for regulating the tension of the spring under the lever.

THE RELAY.

The Relay consists, as shown in Fig. 10, of a large intensity electro-magnet, supported by a frame of brass on a dry hard wood base. The armature of the electro-magnet is attached to a lever, which plays between two adjustable set screws, fixed in the frame of the instrument. As this lever acts as a key to open and close the local circuit, it is provided with a platinum point which strikes upon another platinum point on the end of the set screw. The platinum point of the lever is in electrical connection, by means of wires beneath the base of the instrument, with one of the binding posts, and the point in the screw, with the other. The wires of the local circuit are connected to these

binding posts. The coils of the magnet are in connection with the binding posts



behind the coils, to which the main line wires are attached, and the magnet put

in circuit. The tension of the spring which draws the armature and its lever back, and opens the local circuit when it is not closed by the attraction of the magnet, is regulated by an adjustment. The distance of the magnet from the armature is regulated by another adjustment, called the "back adjustment."


The coils of relay magnets are wound with very fine wire, usually No. 30 to No. 36, and with a resistance varying to suit the resistance of the circuit. The coils of electro-magnets used in telegraphy are generally covered with hard rubber, as a protection to the wire.

THE SOUNDER.

The *Sounder*, or receiving instrument is shown in Fig. 11. It consists simply of a small electro-magnet, having a resistance of from 2 to 4 ohms; an armature and heavy sounding lever, which plays between two adjustable set-screws; and the necessary frame-work of brass, mounted upon a base of wood. An adjustment is provided for regulating the tension of the spring of the armature. The

magnet is put in circuit by means of two binding posts on the base of the instrument.

Fig. 11.




The Sounder.

MAIN LINE SOUNDERS.

When the current of the main circuit is sufficiently strong, the local circuit and sounder is sometimes dispensed with, and the relay is converted into a sounder by giving its lever more “play,” or motion, and thereby increasing its sound. More frequently a *Main Line Sounder* is used. This instrument is made in a variety of forms, and numerous devices have been

Fig. 12.



Box Relay.


employed to increase the sound of the lever, which must often be operated by a comparatively weak main line current.

THE BOX RELAY.

The instrument called the *Box Relay* is so arranged that it may be used advantageously either as a relay or as a main line sounder. The magnet coils are inclosed in a small wooden box against which the lever strikes (Fig. 12), thus increasing the sound. These instruments, when made with a key upon the same base, are convenient portable instruments for opening temporary offices.

NOTE.—The form of key now in general use has a lever of steel made in a single piece with the trunnion shaft. Fig. 13 is a combination set, showing such a key, with relay and sounder, of the most modern pattern, on one base. These instruments, either in combination or separately, the quadruplex machinery, switches, etc., as well as the galvanometer and rheostat shown in Part I, are illustrations of apparatus manufactured by J. H. Bunnell & Co., 76 Cortlandt Street, New York.

Fig. 13




Morse Combination Set.

CUT-OUTS AND OTHER SWITCHES.

When an office is left with no one in charge the wires should be "cut out," or disconnected from the line. The cut-out is made in various simple forms, usually combined with a ground switch, and sometimes with a lightning arrester. The form called the *plug switch* (Fig. 14) has been extensively used. A plug is made of two pieces of brass separated and insulated from each other by a piece of hard rubber. The instruments of the office are connected with the two sides of this plug by flexible conducting wires. When the office is to be put in circuit, or "cut in," the plug is inserted between a pin and a brass spring, as shown in the figure. The main line wires are attached to the binding posts at the top of the switch, one of which is in connection with the pin, and the other with the brass spring. It is obvious that as the two sides of the plug are insulated from each other the current must pass through the office; but when the plug is with-

drawn the brass spring presses against the pin, closing the main circuit, and

Fig. 14.




Plug Switch.

leaving the office entirely disconnected, or "cut out." The switch shown has

ground switch and lightning arrester at the top.

A later form, called a *spring cut-out*, is shown by Fig. 14a. The plug is cylindrical, and the operation of the cut-

Fig. 14a.



Spring Cut-Out.

out device is obvious. The figure shows cut-outs for four wires. They are usually made for from one to three lines in connection with ground connectors and lightning arresters, and may be used

wherever it is not required to make cross connections of wires, or any changes other than changing instruments from one line to another. Other forms of switches are used, and for various purposes, but they are too numerous to be described within the limits of this little book.


LIGHTNING ARRESTERS.

The fine wire coils of the relay magnet are sometimes burned or injured by atmospheric electricity, which follows the wires into the office during the prevalence of electric storms. As a protection, *lightning arresters* are sometimes used. Both the line and ground wires are attached to the lightning arrester, so that a charge of atmospheric electricity entering the office by the line wires is carried to the ground. The lightning arrester is made in several forms, but the principle involved is much the same in all of them: that is, that atmospheric electricity, being of high intensity, will leap a slight break in the conductor, or overcome con-

siderable resistance in order to force its way to the ground; while the galvanic current, being of lower intensity, is unable to overcome such resistance and is confined to the line.

A common form, the *disc arrester*, is shown in Fig. 15. A disc of brass is

Fig. 15.




Disc Arrester.

screwed over brass plates connecting with line and ground, but not quite touching them. Another form is arranged with pointed screws projecting from the line-wire plates toward the ground-wire plate, leaving a very small space between the plate and the points, over which the lightning leaps, making its way to the

ground. (See Fig. 14.) Other forms have notches or “saw teeth” projecting from one plate in proximity to another. The *plate arrester* does not vary materially in principle from the disc arrester. In the *quadruplex arrester* (Fig. 15a) a very fine coil of wire is fused by the light-

Fig. 15a.



Quadruplex Arrester.


ning, thus making connection with the ground plate. It is commonly used with quadruplex apparatus as a protection to the finely wound magnets of the relays.

THE SWITCH BOARD.

A *switch board* is generally used in offices having two or more wires entering them. The form now in common use is

shown in Fig. 16. The connections of brass are arranged upon a board of dry hard wood, as represented, and fitted

Fig. 16.



Switch Board.

with binding posts at the top, to which the line wires are connected. Other straps of brass pass horizontally across

the back of the board, and are in connection with the binding posts at the side of the board, to which the instrument wires are connected. Each of these back straps is in connection with one of the horizontal rows of studs which appear between the line straps upon the face of the board. By inserting plugs in the holes between the studs and line straps connection is made with the instrument straps. It is clear that any instrument may now be connected with any line wire, and a little study of the connections will show that any two line wires may be cross connected, or that any desired wire east from the office may be connected to any other wire west, or any required changes in the wire connections be made. The lowest row of studs is connected with the ground wire. By inserting a plug at the bottom of the board, connecting the east and west line straps together, the wire is cut out. The board shown is provided with disc lightning arresters.

Large switch boards are often fitted with *spring jacks* for cutting in the instruments, the straps being then used only for cross connections, battery connection, etc., thus rendering a much fewer number of horizontal connectors necessary. Otherwise, the board would often be of an inconvenient or impracticable height if horizontal connections were required for every instrument.

The spring jack consists essentially of a plate or strap of brass upon which the jack, also of brass, is held firmly by means of a spring. Each of these is in connection with one of the ordinary board straps to which the two ends of the line wire are connected, and which are thus effectually cut out. The instrument wires are connected through a flexible conducting cord, similar to that used with the ordinary plug switch, with the two brass sides of a wedge which are separated and insulated from each other by hard rubber. When this wedge is inserted between the jack and the lower plate the instrument is cut in.

LOOPS.

What is technically termed a “loop” in telegraphy, is a wire branching off from the main circuit, running to some point and returning again to the line. A loop is arranged so that it may be cut out from the line if necessary. A plug switch is the most convenient for this purpose, the switch being put in circuit at the office where the loop commences, and the wires of the loop attached to the plug.

ARRANGEMENT OF OFFICES.

In the arrangement of offices, the line wire entering the office first passes through the cut-out switch and lightning arrester, and then through the key and the magnet of the relay. It is immaterial which of these latter instruments is first in order in the circuit, as long as they are all properly connected. The circuit, after passing through the apparatus, is made complete to the ground, if it is a terminal office; or runs back through the lightning

arrester and cut-out, out of the office and on toward the next station, if it is a way station. The connections of the local circuit, which is entirely confined to the office, may be understood by reference to Fig. 8.


ARRANGEMENT OF BATTERIES.

Two batteries are generally used on the main circuit, one at each end. The number of cells in each battery is equal under ordinary circumstances, and the number will depend upon the length and resistance of the circuit. Not only should the different cups of each battery be connected with regard to the law of attraction and repulsion, but the batteries at each end of the line should be placed with *opposite poles to the line*, in accordance with the same law. Frequently, several wires are worked from the same battery on the principle of a “divided circuit”; and in this case it is important that the wires should equal each other in resistance as nearly as possible.

REPEATERS.

When the length of a telegraph circuit renders it of too great resistance to be worked satisfactorily, the circuit is divided into two or more parts, and a *repeater* is

Fig. 17.



Repeater.

used. The repeater “repeats,” or transmits the signals received on one circuit into the other, much in the same way as the relay repeats the signals from the main into the local circuit. The re-

peater must be arranged so as to transmit from *either* circuit into the other, according to the direction in which the message may be going.

The connections of a simple "switch repeater" are shown in Fig. 17. M and M' are the relay magnets of the eastern and western circuits respectively; and S and S' are the sounders of the eastern and western circuits; B and B the main-line batteries. The local circuits connect the sounders with the relays in the ordinary manner, but the local wires are omitted in the figure, in order to avoid confusion of the lines.

The sounders, S S', are of a peculiar construction, their levers being provided with platinum points, similar to those of a relay. The opposite main circuit passes through the lever and platinum points of each sounder, so that, as the sounder is worked by its relay, it repeats the signals through its platinum points into the opposite circuit.

With the switch, R, in the position shown in the figure, the two circuits

work through, not as a repeater, but as a single circuit. This may be seen by tracing the connections in the figure. It should be remembered that the wires *do not touch each other* at points where they are represented as *crossing* each other. By connecting the ground wire by means of the ground switch, GS, the through circuit is divided into two distinct and independent circuits.

When the apparatus is arranged as a repeater, the ground wire is also connected. When the switch, R, is turned so as to connect the points W and W, the western sounder, S, repeats into the eastern circuit. When the switch, R, is turned so as to connect the points E and E, the reverse operation takes place, and the eastern sounder, S'; repeats into the western circuit. The operation may be readily understood by carefully tracing the connections with the lever, R, in the several different positions named.

It will be noticed that the switch must be turned every time the sending changes from one circuit to the other. Several


forms of “automatic repeaters” are in use, in which this result is automatic, the only attention necessary being in keeping the apparatus properly adjusted.

AUTOMATIC REPEATERS.

Of the various forms of automatic repeaters, the Milliken-Hicks repeater has been adopted by the Western Union Telegraph Company as their standard. The principle of its operation may be understood by reference to the diagram, Fig. 1S. The relay is shown in Fig. 18*a*.

Each circuit passes through the larger magnet of the relay, and repeating points of the repeating sounder, to ground. The local circuit connects contact points of relay with the sounder magnet in the usual manner. An extra local circuit runs through the extra magnet, X, of the relay and the extra contact points of the sounder on the opposite side. Now, let the west circuit open key. Relay R opens, and through its local circuit opens sounder S, which opens the east circuit


Fig. 18.



Miliken-Hicks Repeater.

at *C*. But *S* at the same time opens the extra local circuit of the extra relay magnet *X'*, and its armature lever falls back and is drawn by the retractile spring firmly against the lever of *R'*, thus pre-

Fig. 18*a*.



Milliken-Hicks Relay.

venting the breaking of the east local circuit, and holding the repeating sounder on that side closed. The east circuit repeats into the west in the same manner. The keys, not shown in the diagram, are connected in the usual manner.

PART III. — THE QUADRUPLEX.

DUPLEX AND QUADRUPLEX SYSTEMS.

A *duplex* telegraph is a system whereby a single line wire is utilized for the simultaneous transmission of two messages—as usually understood, one in each direction.

A *quadruplex* telegraph is a system whereby a single line wire is utilized for the simultaneous transmission of four messages—two in each direction.

Experiments in duplex transmission were made in England, Austria, and Germany as early as the year 1853, but nothing of practical value seems to have been accomplished until 1868, when J. B. Stearns of Boston introduced his duplex system upon the lines of the Franklin Telegraph Company. It was not until 1872 that improvements were made by the same inventor which rendered his system practicable upon long lines. The quadruplex was invented by T. A. Edison in 1874, and important

improvements were made later by various American electricians.

The polar duplex is still in use, and an examination of the principles involved in both that and the Stearns system will be necessary as preliminary to the study of the quadruplex.

THE STEARNS DUPLEX.


In studying any system of double transmission, consider that it is only essential that each relay shall respond freely to the signals transmitted from the distant station, without interference from those transmitted at its own station, by which it remains entirely unaffected.

Reference is first made to principles stated in Part I.: When a current divides between two branches of a circuit, equal currents will traverse branches of equal resistance. When currents of equal strength pass in opposite directions through the coils of an electro-magnet, no magnetic effect is manifested.

The principle of the Stearns duplex may be readily understood by reference

to Fig. 19, which shows connections at one end of the line, station A, only, the connections at station B being identical. N is a differentially wound or neutral relay, T a single-current transmitter, R


Fig. 19.



Stearns Duplex.

a rheostat, and B the battery. The key, K, is not located in the main circuit, but operates the transmitter through a local battery and connections, L, the transmitter itself performing the service of opening and closing the main circuit.

The transmitter lever and connections are shown on a larger scale by Fig. 19*a*, G representing the ground connection, T the line, and B the battery connection. The position shown is when key is closed and magnet M attracts its armature. The opposite end of the lever is now

Fig. 19*a*.

Transmitter Connections.

elevated, and the spring, S, which is insulated from the lever, is brought into contact with the set-screw, making connection from battery to line. When key is open the same end of the lever moves downward, breaking contact with B, and spring S presses upward, making contact with C, establishing connection between

ground and line. Thus, when the key is closed battery is to line, when it is open line is to ground.

The current from T divides at *d* (Fig. 19), passing in opposite directions through the coils of the neutral relay, one branch through the rheostat circuit to ground, the other to line. The resistance of the rheostat being adjusted to make these currents of equal strength, no magnetic effect is produced in the relay. That portion of the current going to line, however, passes through the line coil only of the relay at the distant station, B, and this current not being balanced by any current through the second coil, the armature of relay at B is attracted in response to signals from A, while the armature of relay at A remains inert.

Now, let key be closed at station B, and a similar effect is produced, but in the opposite direction, relay B remaining unaffected while relay A responds. These effects are produced during simultaneous transmission from both ends of the line, whether the keys are closed simulta-

neously or not. If A closes key at the same instant with B, the neutral effect is produced in both relays by the current




Fig. 190.

Transmitter.

from the home battery, but each receives an additional strength of current from the distant station through the line coil of its relay which moves the arma-

ture. Thus, under all conditions, each relay is unaffected by signals sent at its own station, while it responds to those from the distant station.


The neutral relay is similar in appearance to the ordinary Morse relay, and operates a sounder through a local battery and connections, not shown in the diagram. The transmitter is shown in Fig. 19*b*.

THE CONDENSER.

A line wire will, to a certain extent, induce electricity in other objects, especially adjacent wires upon the same route, and thus, acting as an electrical condenser, will take up an additional charge. In the duplex, when the transmitter suddenly cuts off the battery and substitutes a route of small resistance to the ground, a portion of this accumulated charge will return to the ground rather than overcome the greater resistance of the line. This return charge is known among operators as the "kick." The result is a momentary magnetization of the relay, which causes a false movement of the

armature. To counteract this a condenser is used, which may be adjusted to counteract the accumulative capacity of the line, and which, discharging itself through

Fig: 20.



Polar Duplex.

the magnet coils in an opposite direction, may neutralize the effect of the kick.

The condenser, as usually constructed, consists of sheets of tin-foil separated by alternate sheets of mica, enclosed in a


flat wooden box. Alternate sheets of tin-foil are connected to line and ground in groups, and any number of groups required may be placed in circuit by means of plugs. C is the condenser in Figs. 19 and 20.

THE POLAR DUPLEX.

The polar relay is shown in Fig. 20*a*. A large permanent magnet of a curved form is mounted upon a base. The electro-magnet cores are differentially wound and fastened to the south pole of the permanent magnet, and so become south poles by induction. The armature lever is connected with the north pole of the permanent magnet, and so its end, projecting between the cores, becomes a north pole by induction. Now, as long as no current passes, both cores are, at their upper ends, south poles, and the lever is attracted equally by them, as long as it is adjusted midway between them, and remains inert.

The *pole-changer* (Fig. 20*b*) is the instrument by means of which the direction of the current is changed, thus producing

Fig. 20a.




Polar Relay.

changes of polarity in the relay. It is operated by a key and local battery.

Fig. 20 is a theoretical diagram of the polar duplex, and shows the operation of the pole-changing device. A thin strip of metal projects from the end of the armature lever, L , which is at all times in connection with the ground. The position shown is when key is open, the armature end of the lever being elevated, while the contact end is depressed, which places the $+$ pole of battery to ground through contact spring c , while the $-$ pole is to line through c' . When key is closed the contact end of lever is elevated, lifting c' from the set-screw below it, and allowing c to come in contact with the set-screw above it, placing $+$ pole to line and $-$ pole to ground.

P is the polar relay, and currents from either C or C' divide at d , one branch through one coil of the relay to line, the other through the second coil of relay and the rheostat, R , to ground. As in the Stearns duplex, the rheostat is balanced to line, and the two branch currents are

Fig. 20b.



Polar Changer.

of equal strength, and passing through the coils in opposite directions, produce no magnetic effect.

Now, suppose the strength of each branch of the current traversing the coils at station A to be represented by 3, and that while the + pole of battery at A is to line we place the — pole of battery to line at the distant station B. Then there will be an additional current having a strength of 3, from battery at B, passing through the line coil at A, and its armature is attracted to s. In like manner, at B the — current from its battery will be augmented by a + strength of 3 from the battery at A through the line coil at B, and its armature also attracted to s.

Now, the first requirement is that each relay shall remain unaffected by changes or polarity of its home battery. Open the pole-changer at A, reversing the poles from + to — to line. Station B still has — pole to line, and the two batteries being now opposed to each other, no current passes through the line coil of relay

at A, but there is still a current flowing in through the second coil, and in the same direction as before the change of polarity, and this repels the armature, which remains as before.


The second requirement is that the armature of either relay shall respond to changes of polarity at the distant station. Let A have + pole to line and let distant station B change from — to +. The two batteries now oppose each other and no current passes through the line coil at A, but a current of 3 still passes through the rheostat branch to ground through the second coil and in a direction opposite to that before the change of polarity at B. Therefore the armature is repelled to *n*. As these effects occur in either direction, each relay responds only to changes of polarity at the distant station.

The use of condenser C is to give a static discharge and prevent the “kick” at the instant of changes of polarity.

THE QUADRUPLIX.

These two systems of double transmission combined, with certain modifica-

Fig. 20c.




Double Transmission in One Direction.

tions, form the quadruplex. The most important modification relates to the Stearns system. In this duplex, which operates on the primary conditions of battery to line and no battery to line, there will be intervals when there is no current on the line from either battery. Again, the polar system operates upon the principle of changes of polarity, and it is evident that when combined with the Stearns duplex the interruption of the current by the Stearns side will interfere with the working of the polar side. This difficulty is overcome in the quadruplex by arranging the battery in two sections, and the transmitter, instead of cutting off battery entirely when the key is open, leaves one third of it in circuit, while the entire battery is in circuit when the key is closed.

Simplify the explanation by reference to Fig. 20c, which is a theoretical diagram showing the combination of the neutral and polar principles to work in one direction only, the two sending instru-

Fig. 20d



Quadruplex Connections.

ments being at station A and the two receiving instruments at station B. The circuit, starting from ground at G, passes to the pole-changer, PC, thence from contact *s* to — pole of battery, from + pole of battery to contact of transmitter T, thence to the other contact *s'* of PC. A *tap wire*, cutting off two thirds of the battery called the *long end*, connects with lever T as a substitute for the ground connection of the Stearns duplex.

At station B, the polar relay, PR, responds only to changes of polarity, or direction of current, without regard to strength. The neutral relay, N, responds only to increase in strength of current without regard to polarity. Thus, PR responds only to PC, and N responds only to T. The polar relay, therefore, intended to respond to changes of polarity in currents of varying strength, is made very sensitive, the coils being usually wound to about 400 ohms resistance in each direction. The neutral relay is less sensitive, being wound to about 200 ohms in each direction, and its retractile spring

is adjusted to such a tension as to resist the attraction of the armature when the transmitter at station A is open, and it receives the strength of only one third of the battery (the *short end*), while it responds when the transmitter is closed and it receives the strength of the whole battery. Thus, the continuity of the circuit is never broken by either T, or PC at station A. T varies the strength of current going to station B, while PC changes its polarity although the signals transmitted by PC may vary in *strength* according to the position of T at the particular instant, and it is evident that each relay at B will respond independently.

The diagram, Fig. 20*d*, shows the actual connections of the quadruplex at one station. The circuits connecting transmitter T, pole-changer PC, and the line coils of neutral relay NR and polar relay PR, and thence to line, are represented by unbroken lines. The branch circuit through the second coils of the relays and rheostat to ground are shown in broken lines. Other connections are in fine dotted lines. The local circuits oper-

ating the transmitter, pole-changer, and sounders, are omitted from the diagram.

Trace the line connections, which run virtually the same as in Fig. 20*c*, from the ground, G, following the figures on the diagram to 6, where the connections with the two back stops of PC unite, thence to ground switch, GS, and resistance box, S. Here the circuit divides for the two coils of the relays, the unbroken lines passing through the first coil of the relays, and lightning arrester, A, to line; the broken lines through the secondary coils, and rheostat, R, to ground at G'. The battery tap wire is shown in fine dotted lines, and it will be noticed that instead of running directly to the transmitter lever, it makes a loop through a small set of resistance coils which are included in the same box with the rheostat. This resistance is adjusted to balance the internal resistance of the long end of the battery, which is cut off by the transmitter when the circuit is through the tap wire, and thus prevent variations of resistance in the circuit resulting from the division of the battery.

At each change of polarity of the battery, the line wire, on long circuits, may accumulate a static charge, producing a kick in the polar relay, and a condenser is used, as shown, to neutralize this effect. At the instant of change of polarity, the armature of the neutral relay also has a tendency to fall back, thus mutilating the signals on the neutral side. This defect is remedied by placing the contact point of the neutral relay on the back stop, and a repeating sounder is substituted for the ordinary local sounder. The repeating sounder again reverses the signals, which are then received on a sounder through an extra local circuit. Now, the time of demagnetization of the neutral relay, during the changes of polarity, is so short that the armature is again attracted before it makes *firm* contact on the back stop, hence the armature of the repeating sounder does not move sufficiently to mutilate the signals as received on the sounder.

The polar side is also called the *No. 1 Side*, and the neutral side the *No. 2 Side*.

PART IV.—PRACTICAL TELEGRAPHY.

ALPHABET AND NUMERALS.

The Morse, or dot and dash alphabet is as follows :

A	--	J	— . — . — .	S	--
B	— . .	K	— . — . — .	T	—
C	-- .	L	— — —	U	-- —
D	— . .	M	— — —	V	— . . —
E	.	N	— .	W	. — — —
F	. — .	O	. .	X	. — . .
G	— — —	P	Y
H	Q	. — . —	Z
I	--	R	&

Period

Comma

Exclamation

Interrogation

The following are the punctuation marks :

1	— — — .	6
2	. — — . .	7	— — — . .
3	. . . — .	8	—
4 —	9	—
5	— — — —	0	— — — —

Several other characters formerly used for punctuation have become obsolete, and combinations of letters are used instead, as “Pn” for *parenthesis*, “Qn” for *quotation*, etc. The combination “Sx” is also used for the dollar sign (\$).

ADJUSTMENT OF INSTRUMENTS.

The proper adjustment of the instruments is always an important duty, and often a difficult one. Under ordinary circumstances, an armature should be adjusted so that there will be about space enough between it and the poles of the magnet, to insert a piece of heavy writing paper, when the armature is attracted toward the magnet. If the armature *touches* the poles of the magnet it will "stick."

In stormy weather, which renders the insulation of the line defective, the magnet of the relay must be drawn back, by means of the adjustment screw, to a greater distance from its armature. The reason of this is, that the escape of the current from the line causes *residual* magnetism in the cores of the relay magnet, which must be counteracted by adjusting back the cores. The spring of the relay armature must be adjusted to suit the strength of the current. In stormy weather adjusting is often exceedingly difficult, and it is sometimes almost impossible to keep the relay working. In

such cases the key should not be opened until the relay is carefully adjusted, to make sure that no other office is using the circuit.

When the key "sticks," or fails to break circuit, it is usually caused either by the platinum points becoming burned and roughened by the passage of the current, or by dirt and dust around the anvil and platinum points, which forms a partial connection when the circuit is opened. The platinum points may be cleaned by a piece of heavy writing paper, or fine emery paper, or, in an extreme case by a very fine file; but much filing of the points should be avoided.

When the relay works properly and the sounder does not work, the fault is in the local circuit. The cause will generally be found in a broken or disconnected wire, or in weakness of the local battery. All the connections and binding posts in an office, especially those of the main circuit, should be carefully watched, and kept closely and firmly screwed up. The lightning arresters should be kept clean,

and always carefully examined after an electric storm.


TESTING TELEGRAPH LINES.

The interruptions which occur in the working of telegraph lines are most commonly caused by *breaks*, *escapes*, or *crosses*. Trouble is also sometimes caused by a loose joint or connection in the circuit, or by the escape of the current from one wire to another on the same poles when they are imperfectly insulated, or by a defective ground wire connection.

BREAKS.

The most common causes of the breaking of the circuit are a key left open, or a broken line wire. When a break occurs the relays will all remain "open," and the result is a total suspension of business upon the circuit. Every operator should proceed to test for the break by connecting the ground wire of his office, first on one side of the instruments and then on the other. Supposing the break to be east of an office, no "circuit" is made

when the ground wire is put on west of the instruments, but when it is put on east of them the circuit of the battery at the




west end of the line is completed through the ground wire, and all offices west of the ground wire can work with each other.

This is made clearer by reference to Fig. 21, which represents a line with three offices, A B C, with a break at F, between B and C. When the ground wire at B is put on west of the office the break interrupts the circuit, but when it is put on east the circuit is complete between A and B, showing that the break is east of B. In this way, it is evident that the fault may be located between some two stations.

ESCAPES.

Escapes often occur, in a greater or less degree, all along a line, from defective insulation, especially during stormy weather. When, however, there is an escape at any particular point, it may be located as follows: The circuit manager should call up the offices in order, beginning with the one at the farther end of the line, and have them open circuit for a moment. When the circuit is open beyond the escape a little current will still pass over the line, completing its circuit through the escape and ground.

On the line shown in Fig. 22 the escape is at F. When the key at C is open there will still be a current at A, which



passes through the escape and ground. When the key at B is open this current is stopped, locating the escape between B and C.


GROUND.

The only difference between an escape and a ground is, that a ground causes the loss of the whole, and an escape of only a part of the current. A ground is tested for and located in the same way as an escape. A ground is often caused by a ground wire being carelessly left on in an office.

CROSSES.

Fig. 23 represents a line with two wires, No. 1 and No. 2, which are crossed between B and C. To locate the cross the circuit manager at A should open No. 2 as shown, and have C open No. 1 and send dots on No. 2. These dots will be transferred at the cross from No. 2 to No. 1 and come on No. 1 at A. If, however, B opens No. 1 and attempts to send dots on No. 2, there is no circuit on either wire, as they are both open, one at A and the other at B, showing that the cross is beyond B.

Fig. 23.



MAINTENANCE OF BATTERY.

To start the battery, place the parts in position, put from $\frac{1}{2}$ to $\frac{3}{4}$ of a pound of sulphate of copper (blue vitriol) in the bottom of the jar, and fill it with water sufficient to cover the top of the zinc.

The battery should be allowed to stand quietly, so as to avoid mixing the solutions, and when newly set up, must stand for several hours on closed circuit before it will develop its normal electro-motive force. Sulphate of copper is composed of oxide of copper and sulphuric acid. It is decomposed by the action of the battery, the copper being separated from the acid and deposited upon the copper plate of the battery in the form of a scaly crust, while the acid attacks the zinc, by which it is constantly consumed, forming sulphate of zinc in the upper part of the jar. The battery, if in proper condition, should show a distinctly marked line of separation of the solutions, although, as usually cared for, it seldom does so. As the sulphate of copper is constantly being dissolved, a few crystals may be dropped to the bottom of the jar once in every two or three days, keeping the blue line of separation up to within about one inch of the bottom of the zinc. On the other hand, the zinc solution is constantly increasing in density, and a little may be

drawn off from time to time by means of a syringe, and replaced by fresh water. The zinc should be removed from the jar occasionally and cleaned with a brush. The battery should be kept clean, and not allowed to freeze, for when frozen the current is weakened or altogether suspended.

BALANCING THE QUADRUPLIX.

The ground switch, GS, in Fig. 20*d*, is used in making the balance of the quadruplex. The distant station is requested to "ground." This cuts out his whole battery and pole-changer, but includes a resistance in the rheostat box, as shown in the diagram, which is equal to the internal resistance of the battery, consequently the balance will be correct when the battery is again cut in. Now, the station making the balance turns his switch to ground also, and line is without battery at either end. Adjust the armature of polar relay so it will remain on whichever side it is placed. Then cut

in full battery and adjust the rheostat until the armature of polar relay will again remain on whichever side it is placed, showing that the resistances of the line and rheostat branches are equal. Finally, open and close the pole-changer and adjust the condenser until the polar relay does not respond to the static charge or discharge of the line.

The polar duplex is balanced in a similar manner.

PART V.—CONSTRUCTION OF LINES.

THE improper and imperfect construction of telegraph lines is often the cause of much unnecessary trouble and waste of material in working them. It is proposed to give, in this chapter, a general idea of the proper construction of a line, with such hints as may be of assistance to students and amateurs in the construction and equipment of private and short lines.

The essential parts of a telegraph line are the conductors, which form a path


for the current, and the insulators, which confine the current to the conductors and prevent its escape to the ground. The poles are not essential to the working of a line, but serve merely as a support for the conductors, which are insulated from them at each point of support.

THE CONDUCTORS.

Galvanized iron is most commonly used for line wire, as plain iron wire is liable to rust, which impairs its conducting power. On the best lines the sizes known as Nos. 8 and 9 are generally used, but a smaller size, as No. 11 or No. 12, will answer for short lines. It should be remembered that the smaller the size of the wire the less is its conducting power, and consequently, the greater the battery power that will be required to work it.

Great care should be exercised in making joints or splices, either in the line or office wires. One loose joint often gives more resistance than a great length of continuous wire. The proper way to make a joint is to twist the end of each

Fig. 24.



Glass Insulator.

wire several times closely around the other, with the several turns of wire at right angles to the line. Wires should never be *hooked* together and bent back upon themselves.

Line wires of hard drawn copper are now in common use, especially for quadruplex and important circuits.

THE INSULATORS.

The glass insulator, shown in Fig. 24, is the most common form. It is made to screw upon a thread cut upon a bracket which is spiked to the side of the pole, or, more frequently, upon a pin which is set in a cross-arm. The line wire is fastened to the insulator by a short piece of wire called *tie wire*, which is passed around a groove in the insulator and its ends twisted around the line wire on each side. The insulator should never be fastened to the bracket by a spike driven over it into the pole, nor should the edge of the insulator be allowed to touch the top edge of the bracket or the side of the

pole, for this forms a connection between the insulator and the pole, causing an escape when the insulator is wet.

Various other forms of insulators are used for ordinary line work, or for special purposes.

FITTING UP OFFICES.

The line wires usually pass into an office directly over a window, and are carried through insulating *window tubes* of hard rubber. An enlarged head is usually made on the end of the tube which is inside the office. The line wire is securely fastened to an insulator outside the office whence it runs through the tube. The end of the wire which projects through the tube is commonly bent into a hook, and the copper office wire spliced to it. A large number of close convolutions should be made around the line wire, and the joint carefully soldered. A better method is to cut a thread upon the end of the line wire, upon which a binding post may be screwed to receive the office wire.

Wires are now frequently brought into offices by using insulated copper wires grouped in cables, which are connected to the line wires within a box fixed to the pole outside the office. A lightning arrester is generally used in connection, the ground wire running down the side of the pole.

Copper wire is used within offices. No. 16 is the most common size, and it is usually insulated by a covering of cotton or linen. It may be fastened to the walls or table whenever desired by small wire staples. The arrangement of the apparatus and batteries has already been explained. Splices in office wires should be very carefully and firmly made.

GROUND-WIRE CONNECTIONS.

Ground wires should be insulated with gutta-percha, or some other material not liable to be affected by exposure to the weather, and firmly attached to a large plate of metal, buried deep enough in the ground to be beyond the reach of frost, and always in connection with moist earth. For a short line a sheet of cop-

per or tin having a surface of several square feet will make a good ground connection. The ground wire should be soldered to the plate, so as to insure a firm contact.

PRIVATE AND SHORT LINES.

A short line may be operated much more economically and satisfactorily by the observance of the proper proportions between the conductors, instruments, and batteries. The rule of the "Proportion of Electro-magnets to the Circuit" has been given in Part I. As it is not often convenient to measure the resistance of short private lines, the approximate resistance per mile of galvanized iron line wires is given below. If the line is well constructed, these figures will approximate to the resistance of the line, under favorable circumstances.

No. 8	wire,	about	16	Ohms	per	mile.
No. 9	"	"	20	"	"	"
No. 10	"	"	24	"	"	"
No. 11	"	"	30	"	"	"
No. 12	"	"	36 $\frac{1}{2}$	"	"	"

For an example, suppose a line one and one-half miles in length, of No. 10 wire. Its resistance by the above figures would be 36 ohms. The resistance of the electromagnets should, according to our rule, equal that of the line. If there are four magnets in circuit they should have a resistance of 9 ohms each, as $36 \div 4 = 9$. This gives a resistance of the whole circuit as follows :

Resistance of Conductor.....	36 Ohms.
“ “ 4 Magnets, 9	
ohms each..	36 “
<hr/>	
Total.....	72 Ohms.

The internal resistance of a battery sufficient to work a line of so light a resistance is so small that it need not be taken into account. Under favorable conditions, 4 cells of Daniell, Hill or Callaud battery will operate this line satisfactorily.

The comparative strength of current with different numbers of cells of battery may be calculated by Ohm's Law, given

in Part 1, thus ;—the electro-motive force of a cell of battery being taken at 56 :—

With 2 cells of battery, electro-motive force is 112, resistance of circuit is 72— $112 \div 72 = 1.55$ effective strength of current.

With 4 cells of battery, electro-motive force is 224, resistance of circuit is 72— $224 \div 72 = 3.11$ effective strength of current.

The resistance of the whole number of electro-magnets should be equal to the resistance of the rest of the circuit, and the resistance of the magnets should be equal *with respect to each other*. Much more satisfactory results can be obtained in the working of a short line by having the magnets made to order of the resistance required. In most cases relays will not be necessary on such a line, but the common local sounders, of a high resistance, may be worked direct by the main line current.

In actual practice better results may be obtained by making the resistance of electro-magnets somewhat less than that

of the other parts of the circuit, making allowance for the defective insulation of the line, as on poorly insulated lines the actual resistance will be considerably reduced during wet weather.

In calculating the resistance of the short lines above considered, the internal resistance of the batteries is not taken into account. In actual practice this should always be considered, and the computation may be made by the following formula :

E. equals the electro-motive force of batteries.

R. “ resistance of the line.

M. “ resistance of the magnets.

B. “ internal resistance of batteries.

C “ strength of the current.

$$\text{Then } C = \frac{E}{R + M + B}$$

APPENDIX.

SUGGESTIONS AND EXERCISES FOR LEARNERS.

It is extremely desirable that a student of telegraphy should commence his practice under the instruction of a competent and thorough operator, but as many students are unable, at first, to obtain such instruction, the following suggestions may be beneficial to them, until they have an opportunity for practice in a regular telegraph office.

An erroneous idea prevails among many learners that it is an easy matter to learn to "send," and that it is proficiency in "receiving," or "reading by sound," only, which is secured by long and diligent practice. The style of sending of different operators varies as much as the style of penmanship of different individuals. If a student learns to send too fast

he will certainly acquire a bad style. A good rule is, never to let the speed of sending exceed the rate at which the same student has learned to receive by sound.

The first part of a student's education is the memorizing of the Morse alphabet, which has been given in another part of this book. When the characters have been learned, they may be practiced upon the key; but, as it is the opinion of experienced instructors that it is better not to practice the alphabet in its regular order, the letters are given hereafter in groups, each one of which forms an exercise which should be practiced until thoroughly mastered before commencing the next.

Attention should be given from the first, to the correct position of the hand in manipulating the key. Place the hand with the first two fingers upon the top of the finger piece of the key, with the thumb at the side, and partly beneath the finger piece. The third and fourth fingers should assume much the same

position as when holding a pen in writing. The arm should rest upon the table at or near the elbow, with the wrist entirely free from the table. Keep the fingers constantly upon the key during manipulation, grasping the key firmly, but not too hard.

The force imparted to the key should be from the wrist, and not from the fingers, the wrist always moving in the same direction with the lever of the key. The pressure should be directly downwards, and not sideways. Let the motion be moderately firm, and give the lever the full vertical motion, so that the downward motion insures a firm contact between the platinum points, and the upward motion the complete breaking of the circuit.

The dots and dashes composing each character are separated from each other by *breaks*, the different characters are separated from each other by *spaces*, and words are separated from each other by a still longer *space*. Correct sending depends upon the perfect proportion in the

length of *dots* and *dashes*, *breaks* and *spaces*.

Practice the following exercises in order. *Do not leave one until it is thoroughly mastered.*

Exercise 1.

E.	I.	S.	H.	P.
-	--	---	----	-----

Make the breaks between the dots **as** short as possible, but let the upward motion of the key be full and free.

Exercise 2.

T.	L.	M.
—	——	———

The dash should be three times the length of a dot. Make the dashes in **M** of equal length and close together. Do not make **T** too long, or **L** too short. **L** should be twice the length of **T**.

Exercise 3.

A.	U.	V.
— —	— — —	— — — —

Exercise 4.

N.

D.

B.

— . .

— . . .

—

Care should be taken to make the letters in the above two exercises compact, and to preserve the proper proportions between dots and dashes.

In the foregoing exercises there are four classes of letters, as follows :

First, dots.

Second, dashes.

Third, dots followed by dashes.

Fourth, dashes followed by dots.

The rest of the exercises include all the remaining letters of the alphabet, which are combinations of those already given.

Exercise 5.

F.

X.

W.

G.

— . .

—

—

—

Q.

K.

J.

—

—

—

The following are called the “spaced

letters," the "space" being just long enough to distinguish it from a "break."

Exercise 6.

O.

R.

&

- -

- - -

- - - -

C.

Z.

Y.

- - -

- - - -

- - - -

The figures and punctuation marks are omitted in the above exercises, as they are more difficult than the letters, and it is better to practice the easier combinations until a complete control is gained over the key. When once the student has become master of the key he will have no difficulty in forming any character, and the figures and punctuation marks may be practiced in order, as given in another part of this book.

Fractions are formed by using a dot to represent the line between numerator and denominator.

In sending large numbers, a space, equal to that used between words, is used

to divide them into periods of three figures each.

After having learned thoroughly all the Morse characters, commence to practice short words, writing slowly and spacing carefully.

Particular care should be exercised in writing words containing spaced letters. The following words present a few examples, which will illustrate the difficulty of writing words containing a number of spaced letters: Ice, Erie, Rice, Cicero, Receive.

No forms for commercial and railroad messages are here given, as these are among the details of telegraph business, with which the student should familiarize himself by actual practice in a regular telegraph office.

INDEX.

- Adjustment of Instruments**, 84.
- Alphabet**—Morse, 83; Exercises for Practicing, 107.
- Ampere**, 20.
- Armature**, 24.
- Arrangement of Batteries**, 55; Cells in, 14.
- Arrangement of Offices**, 54.
- Attraction and Repulsion**—Law of Electrical, 9.
- Automatic Repeaters**, 59.
- Balancing the Quadruplex**, 93.
- Batteries**—Arrangement of, 55; Electrical Quantity and Tension of, 14; Galvanic, 11.
- Battery**—Arrangement of Cells in, 14; Care of, 91; Gravity, 15; Poles of a, 12. Setting up, 91.
- Box Relay**, 43.
- Breaks**—Testing for, 86.
- Cables**—Wires grouped in, 99.
- Cells**—of a Battery, Arrangement of, 14.
- Circuit**—Galvanic, 9; Local, 33; Metallic, 29: Proportion of Electro-magnets to, 27; Telegraph, 29.

Circuits—Divided, 21.

Condensers, 68.

Conductors—of a Telegraph Line, 95.

Conductors and Non-Conductors, 10.

Construction of Lines, 94.

Copper Line Wires, 97.

Crosses—Testing for, 90.

Current—Direction of the, 12; Electric, 9. Galvanic or Voltaic, 9; Unit of, 20.

Currents—Measurement of, 20.

Cut-Outs, 45; Plug, 45; Spring, 47; Spring Jack, 53.

Differential Magnets, 25.

Direction of Current, 12.

Divided Circuits, 21.

Double Transmission—in one direction, 77.

Duplex Telegraphs, 62; Polar, 70; Stearns, 63.

Edison—Inventor of the Quadruplex, 62.

Electric Current, 9.

Electrical Quantity and Tension, 13.

Electricity, 9; Galvanic or Voltaic, 11; Positive and Negative, 9.

Electro-Magnets, 23; Differential, 25; Poles of, 25; Proportions of, 28.

Electro-motive Force, 17; Unit of, 18.

Energy—Electrical, 18.

Escapes—Testing for, 88.

Exercises for Learners, 104.

Faults—In Line, 86; in Local Circuit, 85.

Fitting up Offices, 98.

Fractions—Sending, 109.

Galvanic Battery, 11.

Galvanic Circuit, 12.

Galvanic Electricity, 11.

Galvanometer, 20.

Glass Insulator, 97.

Gravity Battery, 15.

Grounds—Testing for, 90.

Ground Switches, 46; 52.

Ground Wires, 35; Connections for, 99.

Induction—Magnetic, 26.

Instruments—Adjustment of, 84; Combination Set of, 44; Main Line, 43.

Insulator—Glass, 27.

Insulators—of Electricity, 10; of a Telegraph Line, 97.

Intensity—of Currents, 13.

Intermediate Offices, 82.

Inventor—of the Telegraph, 28; of the Quadruplex, 62.

Joints in Wires, 95, 98.

Key, 35; Manipulation of, 105; Sticking of, 85.

Kick—the, 68.

Law—Ohm's, 18.

Laws of the Current, 9, 12, 18, 27.

Lessons for Learners, 104.

Lightning Arresters, 48, 49, 50; Care of, 85.

Lines—Construction of, 94; Private and Short, 100; Testing of, 86.

Line Wires, 95; Copper, 97; Joints in, 95; Resistance of, 100; Sizes of, 95.

Local Circuit, 33; Faults in, 85.

Loops, 54.

Long End—of Battery, 79.

Magnets—Electro, 23; Armature of, 24; Differential, 25; Polarized, 70; Poles of, 26; Proportions of, 28; Proportion of to Circuit, 29; Relay, 40; Sounder, 40.

Maintenance of Battery, 91.

Magnetic Induction, 26.

Magnetism—Residual, 27; Induced, 26.

Measurement—of Currents, 20; of Resistance, 20.

Metallic Circuit, 29.

Milliken-Hicks Repeater, 59; Relay, 61.

Morse, 28; Alphabet, 83; Telegraph, 28.

Neutral Relay, 68.

Offices, Arrangement of, 54; Fitting up, 98; Intermediate, 32; Wires in, 99.

Office Wires, 99.

Ohm, 17.

Ohm's Law, 18.

- Plug Switch**, 45.
- Polar Duplex**, 70; Balancing the, 94.
- Polar Relay**, 70.
- Pole Changer**, 70.
- Poles**--of a Battery, 12; of a Magnet, 25.
- Positive and Negative**--Electricity, 9; Poles of a Battery, 12.
- Potential**--Electrical, 18; Unit of, 18.
- Practical Telegraphy**, 83.
- Private Lines**, 100.
- Proportion**--of Electro-Magnet to Circuit, 27.
- Proportions**--of Electro-Magnets, 28.
- Quadruplex**, 75; Balancing the, 93; Invention of, 62; Polar Side of, 82; Neutral Side of, 82.
- Quantity**--Electrical, 13.
- Relay**--Morse, 38; Box, 43; Milliken-Hicks, 61; Neutral, 68; Polar, 70.
- Repeaters**, 56; Automatic, 59; Milliken-Hicks, 59; Switch, 57.
- Residual Magnetism**, 27.
- Resistance**, 17; Measurement of, 20; of Line Wires, 100; Unit of, 17.
- Rheostat**, 20.
- Short End**--of Battery, 80.
- Short Lines**, 100.
- Single Current Transmitter**, 65.
- Sounder**--Main Line, 41; Morse, 40; Repeating, 57.

- Splices**—in Wires, 95, 98.
Spring Cut-Out, 47.
Spring Jack, 53.
Stearns Duplex, 63.
Switch—Plug, 45; Spring Cut-Out, 47.
Switch Board, 50.

Tap Wire, 79, 81.
Telegraph—Duplex, 62; Invention of, 28;
Morse, 28; Quadruplex, 62, 75.
Telegraph Circuit, 29.
Telegraph Lines—Construction of, 94; Insula-
tion of, 97; Private, 100; Testing of, 86.
Telegraphy—Practical, 83.
Tension—Electrical, 14.
Testing Telegraph Lines, 86.
Tie Wires, 97.
Transmitter—Single Current, 65.

Units—Of Current, 20; Of Electro-motive
Force, 18; Of Potential, 18; Of Resistance,
17.

Volt, 18.
Voltaic Electricity, 11.

Window Tubes, 98.
Wires—Copper Line, 97; Joints in, 95, 98;
Resistance of, 100; Sizes of, 95.

CATALOGUE

OF THE

SCIENTIFIC PUBLICATIONS

OF

D. VAN NOSTRAND COMPANY,

23 MURRAY STREET AND 27 WARREN STREET, N. Y.

A. B. C. CODE. (See Clausen-Thue.)

ABBOTT (A. V.). The Electrical Transmission of Energy. A Manual for the Design of Electrical Circuits. Second edition, revised. Fully illustrated. 8vo, cloth..... \$4 50

ABBOT (Gen'l HENRY L.). The Defence of the Seacoast of the United States. Lectures delivered before the U. S. Naval War College. 8vo, red cloth. 2 00

ADAMS (J. W.). Sewers and Drains for Populous Districts. Embracing Rules and Formulas for the dimensions and construction of works of Sanitary Engineers. Fifth edition. 8vo, cloth. 2 50

A1. CODE. (See Clausen-Thue.)

AIKMAN (C. M., Prof.). Manures and the Principles of Manuring. 8vo, cloth..... 2 50

ALEXANDER (J. H.). Universal Dictionary of Weights and Measures, Ancient and Modern, reduced to the Standards of the United States of America. New edition, enlarged. 8vo, cloth 3 50

ALEXANDER (S. A.). Broke Down: What Should I Do? A Ready Reference and Key to Locomotive Engineers and Firemen, Round House Machinists, Conductors, Train Hands and Inspectors. With 5 folding plates. 12mo, cloth..... 1 50

ALLEN (C. F.). Tables for Earthwork Computation. 8vo, cloth 1 50

ANDERSON (J. W.). The Prospector's Hand-book ; A Guide for the Prospector and Traveller in search of metal-bearing or other Valuable Minerals. Seventh edition, thoroughly revised and much enlarged. 8vo, cloth..... 1 50

ANDERSON (WILLIAM). On the Conversion of Heat into Work. A Practical Hand-book on Heat-Engines. Third edition. Illustrated. 12mo, cloth. 2 25

ANDES (LOUIS). Vegetable Fats and Oils; their Practical Preparation, Purification and Employment for various purposes. Their Properties. Adulteration and Examination. A Hand-book for Oil Manufacturers and Refiners, Candle, Soap and Lubricating Oil Manufacturers and the Oil and Fat Industry in general. Translated from the German. With 94 illustrations. 8vo, cloth..... 4 00

— Animal Fats and Oils. Their Practical Production, Purification and Uses for a great variety of purposes, their Properties, Falsification and Examination. A Hand-book for Manufacturers of Oil and Fat Products, Soap and Candle Makers, Agriculturists, Tanners, etc. Translated by Charles Salter. With 62 illustrations. 8vo, cloth.... net 4 00

ARNOLD (Dr. R.). Ammonia and Ammonium Compounds. A Practical Manual for Manufacturers, Chemists, Gas Engineers and Drysalters. Second edition. 12mo, cloth..... 2 00

ARNOLD (E.). Armature Windings of Direct Current Dynamos. Extension and Application of a General Winding Rule. Translated from the original German by Francis B. DeGress, M. E. With numerous illustrations..... (In Press.)

ATKINSON (PHILIP). The Elements of Electric Lighting, including Electric Generation. Measurement, Storage, and Distribution. Ninth edition. Fully revised and new matter added. Illustrated. 12mo, cloth.. 1 50

— The Elements of Dynamic Electricity and Magnetism. Third edition. 120 illustrations. 12mo, cloth 2 00

- ATKINSON (PHILIP).** Power Transmitted by Electricity and its Application by the Electric Motor, including Electric Railway Construction. New edition, thoroughly revised, and much new matter added. Illustrated 12mo, cloth.... 2 00
- Elements of Static Electricity, with full description of the Holtz and Topler Machines and their mode of operating. Illustrated. 12mo, cloth..... 1 50
- AUCHINCLOSS (W. S.).** Link and Valve Motions Simplified. Illustrated with 29 woodcuts and 20 lithographic plates, together with a Travel Scale, and numerous useful tables, Thirteenth edition, revised. 8vo, cloth..... 2 00
- AXON (W. E. A.).** The Mechanic's Friend. A Collection of Receipts and Practical Suggestions. 12mo, cloth 1 50
- BACON (F. W.).** A Treatise on the Richards, Steam-Engine Indicator, with directions for its use. By Charles T. Porter. Revised, with notes and large additions as developed by American practice; with an appendix containing useful formulæ and rules for engineers. Illustrated. Fourth edition. 12mo, cloth 1 00
- BADT (F. B.).** New Dynamo Tender's Hand book. With 140 illustrations. 18mo, cloth..... 1 00
- Bell Hangers' Hand-book. With 97 illustrations. Second edition. 18mo, cloth..... 1 00
- Incandescent Wiring Hand-book. With 35 illustrations and five tables. Fifth edition. 18mo, cloth. 1 00
- Electric Transmission Hand-book. With 22 illustrations and 27 tables. 18mo, cloth..... 1 00
- BALE (M. P.).** Pumps and Pumping. A Hand-book for Pump Users. 12mo, cloth..... 1 00
- BARBA (J.).** The Use of Steel for Constructive Purposes. Method of Working, Applying, and Testing Plates and Bars. With a Preface by A. L. Holley, C. E. 12mo, cloth..... 1 5
- BARKER (ARTHUR H.).** Graphic Methods of Engine Design. Including a Graphical Treatment of the Balancing of Engines. 12mo, cloth.... 1 5

-
- BARNARD (F. A. P.).** Report on Machinery and Processes of the Industrial Arts and Apparatus of the Exact Sciences at the Paris Universal Exposition, 1867. 152 illustrations and 8 folding plates. 8vo, cloth 5 00
- BARNARD (JOHN H.).** The Naval Militiaman's Guide. Full leather, pocket form..... 1 25
- BARWISE (SIDNEY, M. D., London).** The Purification of Sewage. Being a brief account of the Scientific Principles of Sewage Purification and their Practical Application. 12mo, cloth. Illustrated. 2 00
- BAUMEISTER (R.).** The Cleaning and Sewage of Cities. Adapted from the German with permission of the author. By J. M. Goodell, C. E. Second edition, revised and corrected, together with an additional appendix. 8vo, cloth. Illustrated..... 2 00
- BEAUMONT (ROBERT).** Color in Woven Design. With 32 Colored Plates and numerous original illustrations. Large 12mo..... 7 50
- BEAUMONT, W. and DUGALD CLERK.** Auto-cars and Horseless Carriages..... (In Press.)
- BECKWITH (ARTHUR).** Pottery. Observations on the Materials and Manufacture of Terra-Cotta, Stoneware, Fire-Brick, Porcelain, Earthenware, Brick, Majolica, and Encaustic Tiles. 8vo, paper. Second edition... .. 60
- BERNTHSEN (A.).** A Text-Book of Organic Chemistry. Translated by George M'Gowan, Ph. D. Third English edition. Revised and extended by author and translator. Illustrated. 12mo, cloth..... 2 50
- BERTIN (L. E.).** Marine Boilers: Their Construction and Working, dealing more especially with Tubulous Boilers. Translated by Leslie S. Robertson, Upward of 250 illustrations. Preface by Sir William White. 8vo, cloth. Illustrated.... .. 7 50
- BIGGS (C. H. W.).** First Principles of Electricity and Magnetism. Being an attempt to provide an Elementary Book for those intending to enter the profession of Electrical Engineering. Second edition. 12mo, cloth. Illustrated..... 2 00

-
- BLAKE (W. P.).** Report upon the Precious Metals. Being Statistical Notices of the principal Gold and Silver producing regions of the world, represented at the Paris Universal Exposition. 8vo, cloth..... 2 00
- Ceramic Art. A Report on Pottery, Porcelain, Tiles, Terra-Cotta, and Brick. 8vo, cloth..... 2 00
- BLAKESLEY (T. H.).** Alternating Currents of Electricity. For the use of Students and Engineers. Third edition, enlarged. 12mo, cloth..... 1 50
- BLOUNT (BERTRAM).** Electro-Metallurgy (In Press.)
- BLYTH (A. WYNTER, M. R. C. S., F. C. S.).** Foods : their Composition and Analysis. A Manual for the use of Analytical Chemists, with an Introductory Essay on the History of Adulterations, with numerous tables and illustrations. Fourth edition, revised and enlarged. 8vo, cloth 7 50
- Poisons : their Effects and Detection. A Manual for the use of Analytical Chemists and Experts, with an Introductory Essay on the growth of Modern Toxicology. Third edition, revised and enlarged. 8vo, cloth..... 7 50
- BODMER (G. R.).** Hydraulic Motors ; Turbines and Pressure Engines, for the use of Engineers, Manufacturers and Students. Second edition, revised and enlarged. With 204 illustrations. 12mo, cloth..... 5 00
- BOILEAU (J. T.).** A New and Complete Set of Traverse Tables, Showing the Difference of Latitude and Departure of every minute of the Quadrant and to five places of decimals. 8vo, cloth. 5 00
- BOTTONE (S. R.).** Electrical Instrument Making for Amateurs. A Practical Hand-book. With 48 illustrations. Fifth edition, revised. 12mo, cloth..... 50
- Electric Bells, and all about them. A Practical Book for Practical Men. With more than 100 illustrations. 12mo, cloth. Fourth edition, revised and enlarged..... 50
- The Dynamo : How Made and How Used. A Book for Amateurs. Eighth edition. 12mo, cloth... 1 00

-
- BOTTONE (S. R.).** Electro Motors: How Made and How Used. A Hand-book for Amateurs and Practical Men. Second edition. 12mo, cloth..... 50
- BONNEY (G. E.).** The Electro-Platers' Hand-book. A Manual for Amateurs and Young Students on Electro-Metallurgy. 60 illustrations, 12mo, cloth.. 1 20
- BOW (R. H.).** A Treatise on Bracing. With its application to Bridges and other Structures of Wood or Iron. 156 illustrations. 8vo, cloth..... 1 50
- BOWSER (Prof. E. A.).** An Elementary Treatise on Analytic Geometry. Embracing Plane Geometry, and an Introduction to Geometry of three Dimensions. 12mo, cloth. Nineteenth edition.... 1 75
- An Elementary Treatise on the Differential and Integral Calculus. With numerous examples. 12mo, cloth. Sixteenth edition.... 2 25
- An Elementary Treatise on Analytic Mechanics. With numerous examples. 12mo, cloth. Twelfth edition.... 3 00
- An Elementary Treatise on Hydro-Mechanics. With numerous examples. 12mo, cloth Fifth edition.... 2 50
- A Treatise on Roofs and Bridges. With Numerous Exercises. Especially adapted for school use. 12mo, cloth. Illustrated.....net 2 25
- Academic Algebra. Third edition. 12mo, cloth.. 1 25
- College Algebra. Fourth edition. 12mo, cloth.. 1 75
- Elements of Plane and Solid Geometry. 12mo, cloth. Second edition..... 1 40
- BOWIE (AUG J., Jun., M. E.).** A Practical Treatise on Hydraulic Mining in California. With Description of the Use and Construction of Ditches, Flumes, Wrought-iron Pipes and Dams; Flow of Water on Heavy Grades, and its Applicability, under High Pressure, to Mining. Fifth edition. Small quarto, cloth. Illustrated..... 5 00
- BURGH (N. P.).** Modern Marine Engineering, applied to Paddle and Screw Propulsion. Consisting of 36 colored plates, 259 practical woodcut illustrations,

and 403 pages of descriptive matter. The whole being an exposition of the present practice of James Watt & Co., J. & G. Rennie, R. Napier & Sons, and other celebrated firms. Thick quarto, half morocco. 10 00

BURT (W. A.). Key to the Solar Compass, and Surveyor's Companion. Comprising all the rules necessary for use in the field; also description of the Linear Surveys and Public Land System of the United States. Notes on the Barometer, Suggestions for an Outfit for a Survey of Four Months, etc. Fifth edition. Pocket-book form, tuck 2 50

CALDWELL, (G. C.), and A. A. BRENNEMAN. Manual of Introductory Chemical Practice. For the use of Students in Colleges and Normal and High Schools. Fourth edition, revised and corrected. 8vo, cloth Illustrated..... 1 50

CAMPIN (FRANCIS). On the Construction of Iron Roofs. A Theoretical and Practical Treatise, with wood cuts and Plates of Roofs recently executed. 8vo, cloth..... 2 00

CARTER (E. T.). Motive Power and Gearing for Electrical Machinery. A Treatise on the Theory and Practice of the Mechanical Equipment of Power Stations for Electric supply and for Electric Traction. 8vo, cloth. Illustrated..... 5 00

CHAMBER'S MATHEMATICAL TABLES, consisting of logarithms of Numbers 1 to 108,000, Trigonometrical, Nautical, and other tables. New edition. 8vo, cloth..... 1 75

CHAUVENET (Prof. W.). New Method of Correcting Lunar Distances, and Improved Method of Finding the Error and Rate of a Chronometer, by Equal Altitudes. 8vo, cloth 2 00

CHRISTIE (W. WALLACE). Chimney Design and Theory. A Book for Engineers and Architects, with numerous half-tone illustrations and plates of famous chimneys. 12mo, cloth..... 3 00

CHURCH (JOHN A.). Notes of a Metallurgical Journey in Europe. 8vo, cloth.... 2 00

CLARK D. (KINNEAR, C. E.). A Manual of Rules, Tables and Data for Mechanical Engineers. Based

on the most recent investigations. Illustrated with numerous diagrams. 1,012 pages. 8vo, cloth. Sixth edition 5 00
 Half morocco 7 50

CLARK D. (KINNEAR, C. E.). Fuel; its Combustion and Economy, consisting of abridgements of Treatise on the Combustion of Coal. By C. W. Williams; and the Economy of Fuel, by T. S. Prideaux. With extensive additions in recent practice in the Combustion and Economy of Fuel. Coal, Coke, Wood, Peat, Petroleum, etc. Fourth edition. 12mo, cloth.... 1 50

— The Mechanical Engineer's Pocket-book of Tables, Formulæ, Rules and Data. A Handy Book of Reference for Daily Use in Engineering Practice. 16mo, morocco. Second edition..... 3 00

— Tramways, their Construction and Working, embracing a comprehensive history of the system, with accounts of the various modes of traction, a description of the varieties of rolling stock, and ample details of Cost and Working Expenses. Second edition. Re-written and greatly enlarged, with upwards of 400 illustrations. Thick 8vo. cloth. 9 00

— The Steam Engine. A Treatise on Steam Engines and boilers; comprising the Principles and Practice of the Combustion of Fuel, the Economical Generation of Steam, the Construction of Steam Boilers, and the Principles, Construction and Performance of Steam Engines, Stationary, Portable, Locomotive and Marine, exemplified in Engines and Boilers of recent date. 1,300 figures in the text, and a series of folding plates drawn to scale. 2 vols. 8vo, cloth. 15 00

CLARK (JACOB M.). A new System of Laying Out Railway Turn-outs instantly, by inspection from Tables. 12mo, leatherette.... 1 00

CLAUSEN-THU (W.). The A. B. C. Universal Commercial Electric Telegraphic Code, especially adapted for the use of Financiers, Merchants, Ship-owners, Brokers, Agent, etc. Fourth edition 8vo, cloth. 5 00

— The A1 Universal Commercial Electric Telegraphic Code. Over 1,240 pp., and nearly 90,000 variations. 8vo, cloth..... 7 50

- CLEEMANN (THOS. M.).** The Railroad Engineer's Practice. Being a Short but Complete Description of the Duties of the Young Engineer in the Preliminary and Location Surveys and in Construction. Fourth edition. Revised and enlarged. Illustrated. 12mo, cloth 1 50
- CLERK (DUGALD).** Auto-cars or Horseless Vehicles. About 300 pp., 60 illustrations..... ..(In Press.)
- CLEVENGER (S. R.).** A Treatise on the Method of Government Surveying as prescribed by the U. S. Congress and Commissioner of the General Land Office, with complete Mathematical, Astronomical and Practical Instructions for the use of the United States Surveyors in the field. 16mo, morocco... .. 2 50
- COFFIN (Prof. J. H. C.).** Navigation and Nautical Astronomy. Prepared for the use of the U. S. Naval Academy. New Edition. Revised by Commander Charles Belknap. 52 woodcut illustrations. 12mo, clothnet. 3 50
- COLE (R. S., M. A.).** A Treatise on Photographic Optics. Being an account of the Principles of Optics, so far as they apply to Photography. 12mo, cloth, 103 illustrations and folding plates..... 2 50
- COLLINS (JAS. E.).** The private Book of Useful Alloys, and Memoranda for Goldsmiths, Jewelers, etc. 18mo, cloth 50
- CORNWALL (Prof. H. B.).** Manual of Blow-pipe Analysis, Qualitative and Quantitative. With a Complete System of Descriptive Mineralogy. 8vo, cloth. With many illustrations..... 2 50
- CRAIG (B. F.).** Weights and Measures. An Account of the Decimal System, with Tables of Conversion for Commercial and Scientific Uses. Square 32mo, limp cloth 50
- CROCKER (F. B.).** Electric Lighting. A Practical Exposition of the Art, for use of Engineers, Students, and others interested in the Installation or Operation of Electrical Plants. Second edition. Revised. 8vo, cloth. Vol. 1. The Generating Plant 3 00
Vol. 2.... ..(In Press.)

-
- CROCKER, (F. B.), and S. S. WHEELER.** The Practical Management of Dynamos and Motors. Fourth edition (eighth thousand). Revised and enlarged. With a special chapter by H. A. Foster. 12mo, cloth. Illustrated..... 1 00
- CUMMING (LINNÆUS, M. A.).** Electricity treated Experimentally. For the use of Schools and Students. New edition. 12mo, cloth..... 1 50
- DAVIES (E. H.).** Machinery for Metalliferous Mines. A Practical Treatise for Mining Engineers, Metallurgists and Manufacturers. With upwards of 300 illustrations. 8vo, cloth 5 00
- DAVIS (JOHN W., C. E.).** Formulæ for the Calculation of Railroad Excavation and Embankment, and for finding Average Haul. Second edition. Octavo, half roan.. 1 50
- DAY (CHARLES).** The Indicator and its Diagrams With Chapters on Engine and Boiler Testing; Including a Table of Piston Constants compiled by W. H. Fowler. 12mo, cloth. 125 illustrations..... 2 00
- DERR (W. L.).** Block Signal Operation. A Practical Manual. Oblong, cloth..... 1 50
- DIXON (D. B.).** The Machinist's and Steam Engineer's Practical Calculator. A Compilation of Useful Rules and Problems arithmetically solved, together with General Information applicable to Shop-Tools, Mill Gearing, Pulleys and Shafts, Steam-Boilers and Engines. Embracing valuable Tables and Instruction in Screw-cutting, Valve and Link Motion, etc. 16mo, full morocco, pocket form... 1 25
- DODD (GEO.).** Dictionary of Manufactures, Mining, Machinery, and the Industrial Arts. 12mo, cloth ... 1 50
- DORR (B. F.).** The Surveyor's Guide and Pocket Table Book. 18mo, morocco flaps. Third edition... 2 00
- DRAPER (C. H.).** An Elementary Text Book of Light, Heat and Sound, with Numerous Examples. Fourth edition. 12mo, cloth. Illustrated.. 1 00
- Heat and the Principles of Thermo-Dynamics. With many illustrations and numerical examples. 12mo, cloth..... 1 50

-
- DUBOIS (A. J.).** The New Method of Graphic Statics. With 60 illustrations. 8vo, cloth..... 1 50
- EDDY (Prof. H. T.).** Researches in Graphical Statics. Embracing New Constructions in Graphical Statics, a New General Method in Graphical Statics, and the Theory of Internal Stress in Graphical Statics. 8vo, cloth 1 50
- Maximum Stresses under Concentrated Loads. Treated graphically. Illustrated. 8vo, cloth..... 1 50
- EISSLER (M.).** The Metallurgy of Gold; a Practical Treatise on the Metallurgical Treatment of Gold-Bearing Ores, including the Processes of Concentration and Chlorination, and the Assaying, Melting and Refining of Gold. Fourth Edition, revised and greatly enlarged. 187 illustrations. 12mo, cloth 5 00
- The Metallurgy of Silver; a Practical Treatise on the Amalgamation, Roasting and Lixivation of Silver Ores, including the Assaying, Melting and Refining of Silver Bullion. 124 illustrations. Second edition, enlarged, 12mo, cloth 4 00
- The Metallurgy of Argentiferous Lead; a Practical Treatise on the Smelting of Silver Lead Ores and the Refining of Lead Bullion. Including Reports on Various Smelting Establishments and Descriptions of Modern Smelting Furnaces and Plants in Europe and America. With 183 illustrations. 8vo, cloth 5 00
- Cyanide Process for the Extraction of Gold and its Practical Application on the Witwatersrand Gold Fields in South Africa. Second edition. Enlarged. 8vo, cloth. Illustrations and folding plates 3 00
- A Hand-book on Modern Explosives, being a Practical Treatise on the Manufacture and use of Dynamite, Gun Cotton, Nitro-Glycerine and other Explosive Compounds, including the manufacture of Collodion-Cotton, with chapters on explosives in practical application. Second edition, enlarged with 150 illustrations. 12mo, cloth..... 5 00
- ELIOT (C. W.), and STORER (F. H.).** A compendious Manual of Qualitative Chemical Analysis. Revised with the co-operation of the authors, by Prof. William R. Nichols. Illustrated. Nineteenth edition, newly revised by Prof. W. B. Lindsay, 12mo. cloth..... 1 25

-
- ELLIOT (Maj. GEO. H.).** European Light-House Systems. Being a Report of a Tour of Inspection made in 1873. 51 engravings and 21 woodcuts. 8vo, cloth 5 00
- ELLISON, (LEWIS M.).** Practical Application of the Indicator. With reference to the adjustment of Valve Gear on all styles of Engines. Second edition, revised. 8vo. cloth, 100 illustrations .. 2 00
- EVERETT (J. D.).** Elementary Text-book of Physics. Illustrated. Seventh edition 12mo, cloth 1 50
- EWING (Prof. A. J.).** The Magnetic Induction in Iron and other metals. 159 illustrations. 8vo, cloth 4 00
- FANNING (J. T.).** A Practical Treatise on Hydraulic and Water-Supply Engineering. Relating to the Hydrology, Hydro-dynamics, and Practical Construction of Water-Works in North America. 180 illustrations. 8vo, cloth. Fourteenth edition, revised, enlarged, and new tables and illustrations added. 650 pages..... 5 00
- FISH (J. C. L.).** Lettering of Working Drawings. Thirteen plates, with descriptive text. Oblong, 9x12½, boards..... 1 00
- FISKE (Lieut. BRADLEY A., U. S. N.).** Electricity in Theory and Practices or, The Elements of Electrical Engineering. Eighth edition. 8vo, cloth 2 50
- FISHER (H. K. C. and DARBY, W. C.).** Students' Guide to Submarine Cable Testing. 8vo, cloth..... 2 50
- FISHER (W. C.).** The Potentiometer and its Adjuncts. 8vo, cloth..... 2 25
- FLEISCHMANN (W.).** The Book of the Dairy. A Manual of the Science and Practice of Dairy Work. Translated from the German. by C. M. Aikman and R. Patrick Wright. 8vo, cloth..... 4 00
- FLEMING (Prof. J. A.).** The Alternate Current Transformer in Theory and Practice. Vol. 1—The Induction of Electric Currents; 611 pages. New edition. Illustrated. 8vo, cloth..... 5 00
- Vol. 2. The Utilization of Induced Currents. Illustrated. 8vo, cloth 5 00
- Electric Lamps and Electric Lighting. Being a course of four lectures delivered at the Royal Institution, April-May, 1894. 8vo, cloth, fully illustrated 3 00

- FLEMING (Prof. J. A.).** Electrical Laboratory Notes and Forms, Elementary and advanced. 4to, cloth, illustrated..... 5 00
- FOLEY (NELSON), and THOS. PRAY, Jr.** The Mechanical Engineers' Reference Book for Machine and Boiler Construction, in 2 parts. Part 1—General Engineering Data. Part 2—Boiler Construction. With fifty-one plates and numerous illustrations, specially drawn for this work. Folio, half mor. ...25 00
- FORNEY (MATTHIAS N.).** Catechism of the Locomotive. Second edition, revised and enlarged. Forty-sixth thousand. 8vo, cloth..... 3 50
- FOSTER (Gen. J. G., U. S. A.).** Submarine Blasting in Boston Harbor, Massachusetts. Removal of Tower and Corwin Rocks. Illustrated with 7 plates. 4to, cloth..... 3 50
- FOSTER (H. A.).** Electrical Engineers' Pocket Book. 1000 pages with the collaboration of Eminent Specialists (In press)
- FOSTER (JAMES).** Treatise on the Evaporation on Saccharine, Chemical and other Liquids by the Multiple System in Vacuum and Open Air. Second edition. Diagrams and large plates. 8vo, cloth.... 7 50
- FOWLER.** Mechanical Engineers' Pocket Book for 1900 1 00
- FOX (WM.), and C. W. THOMAS, M. E.** A Practical Course in Mechanical Drawing. 12mo, cloth with plates 1 25
- FRANCIS (JAS. B., C. E.).** Lowell Hydraulic Experiments. Being a selection from experiments on Hydraulic Motors, on the Flow of Water over Weirs, in open Canals of uniform rectangular section, and through submerged Orifices and diverging Tubes. Made at Lowell, Mass. Fourth edition, revised and enlarged, with many new experiments, and illustrated with 23 copper-plate engravings. 4to, cloth.....15 00
- FROST (GEO. H.).** Engineer's Field Book. By C. S. Cross. To which are added seven chapters on Railroad Location and Construction. Fourth edition. 12mo, cloth.... 1 00

- FULLER (GEORGE W.).** Report on the Investigations into the Purification of the Ohio River Water at Louisville, Kentucky, made to the President and Directors of the Louisville Water Company. Published under agreement with the Directors. 4to, cloth. 3 full page plates.....net 10 00
- GEIPEL (WM.), and KILGOUR, (M. H.)** A Pocketbook of Electrical Engineering Formula. Illustrated. 18mo, morocco..... 3 00
Large paper edition, wide margins. 8vo, morocco, gilt edges 5 00
- GERBER (NICHOLAS).** Chemical and Physical Analysis of Milk, Condensed Milk and Infant's Milk-Food. 8vo, cloth.... 1 25
- GIBBS (WILLIAM F.).** Lighting by Acetylene, Generators, Burners and Electric Furnaces. With 66 illustrations. Second edition revised. 12mo, cloth.. 1 50
- GILLMORE (GEN. Q. A.).** Treatise on Limes, Hydraulic Cements, and Mortars. Papers on Practical Engineering, United States Engineer Department, No 9, containing Reports of numerous Experiments conducted in New York City during the years of 1858 to 1861, inclusive. With numerous illustrations. 8vo cloth.... 4 00
- Practical Treatise on the Construction of Roads. Streets, and Pavements, with 70 illustrations. 12mo, cloth. 2 00
- Report on Strength of Building Stones in the United States, etc. 8vo, illustrated cloth 1 00
- GOLDING (HENRY A.).** The Theta-Phi Diagram. Practically applied to Steam, Gas, Oil and Air Engines. 12mo, cloth. Illustrated.net 1 25
- GOODEVE (T. M.).** A Text-Book on the Steam Engine. With a Supplement on Gas-Engines. Twelfth Edition, enlarged. 143 illustrations. 12mo, cloth... 2 00
- GORDON (J. E. H.).** School Electricity. Illustrations. 12mo, cloth..... 2 00
- GORE (G., F. R. S.).** The Art of Electrolytic Separation of Metals, etc. (Theoretical and Practical.) Illustrated. 8vo, cloth.... 3 50
- Electro Chemistry Inorganic. Third Edition. 8vo, cloth..... 80

-
- GOULD (E. SHERMAN).** The Arithmetic of the Steam Engine. 8vo, cloth..... 1 00
- GRIFFITHS (A. D., Ph. D.).** A Treatise on Manures, or the Philosophy of Manuring. A Practical Handbook for the Agriculturist, Manufacturer and Student. 12mo, cloth..... 3 00
- GROVER (FREDERICK).** Practical Treatise on Modern Gas and Oil Engines. 8vo, cloth. Illustrated 2 00
- GURDEN (RICHARD LLOYD).** Traverse Tables: computed to 4 places Decimals for every $^{\circ}$ of angle up to 100 of Distance. For the use of Surveyors and Engineers. New Edition. Folio, half morocco. . . 7 50
- GUY ARTHUR (F.).** Electric Light and Power, giving the Result of Practical Experience in Central Station Work. 8vo, cloth. Illustrated.. . . . 2 50
- HAEDER (HERMAN C. E.).** A Hand book on the Steam Engine. With especial reference to small and medium sized engines. English edition re-edited by the author from the second German edition, and translated with considerable additions and alterations by H. H. P. Powels. 12mo, cloth. Nearly 1100 illustrations.... 3 00
- HALL (WM. S. Prof.).** Elements of the Differential and Integral Calculus. Second edition. 8vo, cloth. Illustrated.....net 2 25
- HALSEY (F. A.).** Slide Valve Gears; an Explanation of the action and Construction of Plain and Cut-off Slide Valves. Illustrated. 12mo, cloth. Sixth edition..... 1 50
- The Use of the Slide Rule. Illustrated with diagrams and folding plates. 16mo, boards..... 50
- HAMILTON (W. G.).** Useful Information for Railway Men. Tenth Edition. revised and enlarged. 562 pages, pocket form. Morocco, gilt..... 2 00
- HANCOCK (HERBERT).** Text Book of Mechanics and Hydrostatics, with over 500 diagrams. 8vo, cloth.... 1 75
- HARRISON (W. B.).** The Mechanics' Tool Book. With Practical Rules and Suggestions for use of Machinists, Iron-Workers, and others. Illustrated with 44 engravings. 12mo, cloth..... 1 50

-
- HASKINS (C. H.).** The Galvanometer and its Uses. A Manual for Electricians and Students. Fourth edition. 12mo, cloth 1 50
- HAWKE (WILLIAM H.).** The Premier Cipher Telegraphic Code Containing 100,000 Words and Phrases. The most complete and most useful general code yet published. 4to, cloth 5 00
- 100,000 Words; Supplement to the Premier Code. All the words are selected from the official vocabulary. Oblong quarto, cloth 4 20
- HAWKINS (C. C.) and WALLIS (F.).** The Dynamo; its Theory, Design and Manufacture. 190 illustrations, 12mo, cloth 3 00
- HAY (ALFRED).** Principles of Alternate-Current Working. 12mo, cloth, illustrated 2 00
- HEAP (Major D. P., U. S. A.).** Electrical Appliances of the Present Day. Report of the Paris Electrical Exposition of 1881. 250 illustrations. 8vo, cloth 2 00
- HEAVISIDE (OLIVER).** Electromagnetic Theory. 8vo, cloth, two volumes (acc.) 5 00
- HENRICI (OLAUS).** Skeleton Structures. Applied to the Building of Steel and Iron Bridges. Illustrated 1 50
- HERRMANN (GUSTAV).** The Graphical Statics of Mechanism. A Guide for the Use of Machinists, Architects, and Engineers; and also a Text-book for Technical Schools. Translated and annotated by A. P. Smith, M. E. 12vo, cloth, 7 folding plates. Third Edition 2 00
- HERMANN (FELIX).** Painting on Glass and Porcelain and Enamel Painting. On the Basis of Personal Practical Experience of the Condition of the Art up to date. Translated by Charles Salter. Second greatly enlarged edition. 8vo, cloth, Illustrations, net 3 50
- HEWSON (WM.).** Principles and Practice of Embanking Lands from River Floods, as applied to the Levees of the Mississippi. 8vo, cloth 2 00
- HILL (JOHN W.).** The Purification of Public Water Supplies. Illustrated with valuable Tables. Diagrams and Cuts. 8vo, cloth, 304 pages 3 00
- The Interpretation of Water Analyses. (In Press)

-
- HOBBS (W. R. P.).** The Arithmetic of Electrical Measurements with numerous examples. Fully Worked, 12mo, cloth..... .50
- HOFF (WM. B., Com. U. S. Navy.).** The Avoidance of Collisions at Sea 18mo, morocco75
- HOLLEY (ALEXANDER L.).** Railway Practice. American and European Railway practice in the Economical Generation of Steam. 77 lithographed plates. Folio, cloth12 00
- HOLMES (A. BROMLEY).** The Electric Light Popularly Explained. Fifth Edition. Illustrated. 12mo, paper40
- HOPKINS (NEVIL M.).** Model Engines and small Boats. New Methods of Engine and Boiler Making with a chapter on Elementary Ship Design and Construction. 12mo, cloth..... .1 25
- HOSPITALIER (E.).** Polyphased Alternating Currents. Illustrated. 8vo, cloth.1 40
- HOWARD (C. R.).** Earthwork Mensuration on the Basis of the Prismoidal Formulae. Containing Simple and Labor-saving Methods of obtaining Prismoidal Contents directly from End Areas. Illustrated by Examples and accompanied by Plain Rules for Practical Uses. Illustrated. 8vo, cloth... .1 50
- HUMBER (WILLIAM, C. E.).** A Handy Book for the Calculation of Strains in Girders and Similar Structures, and their Strength; Consisting of Formulae and Corresponding Diagrams, with numerous details for practical application, etc. Fourth Edition. 12mo, cloth..... .2 50
- HURST (GEORGE H.).** Colour; A Hand-book of the Theory of Colour. Containing ten coloured plates and 72 diagrams. 8vo, cloth. Illustrated. Price.... .2 50
- Lubricating Oils, Fats and Greases. Their Origin, Preparation, Properties, Uses and Analysis. 313 pages, with 65 illustrations. 8vo, cloth..... .3 00
- Soaps; A Practical Manual of the Manufacture of Domestic, Toilet and other Soaps. Illustrated with 66 Engravings. 8vo, cloth... .5 00

-
- HUTCHINSON (W. B.).** Patents and How to Make Money out of Them. Member of New York Bar. 12mo, cloth. New York, 1899 1 25
- HUTTON (W. S.).** Steam Boiler Construction. A Practical Hand-book for Engineers, Boiler Makers and Steam Users. Containing a large collection of rules and data relating to recent practice in the design, construction, and working of all kinds of stationary, locomotive and marine steam boilers. With upwards of 500 illustrations. Third edition. Carefully revised and much enlarged. 8vo, cloth... 6 00
- Practica Engineer's Hand-book, Comprising a treatise on Modern Engines and Boilers, Marine, Locomotive and Stationary. Fourth edition. Carefully revised with additions. With upwards of 570 illustrations. 8vo, cloth..... 7 00
- The Works' Manager's Hand-book of Modern Rules, Tables, and Data for Civil and Mechanical Engineers. Millwrights and Boiler Makers, etc., etc. With upwards of 150 illustrations. Fifth edition. Carefully revised, with additions. 8vo, cloth..... 6 00
- INNES (CHARLES H.).** Problems in Machine Design. For the Use of Students, Draughtsmen and others. 12mo, cloth..... 1 50
- Centrifugal Pumps, Turbines and Water Motors. Including the Theory and Practice of Hydraulics 12mo, cloth..... 1 50
- ISHERWOOD (B. F.).** Engineering Precedents for Steam Machinery. Arranged in the most practical and useful manner for Engineers. With illustrations. 2 vols. in 1. 8vo, cloth..... 2 50
- JAMESON (CHARLES D.).** Portland Cement. Its Manufacture and Use. 8vo, cloth..... 1 50
- JAMIESON (ANDREW C. E.).** A Text-Book on Steam and Steam Engines. Specially arranged for the use of Science and Art, City and Guilds of London Institute, and other Engineering Students. Tenth edition. Illustrated. 12mo, cloth..... 3 00
- Elementary Manual on Steam and the Steam Engine. Specially arranged for the use of First-Year Science and Art, City and Guilds of London Institute, and other Elementary Engineering Students. Third edition. 12mo, cloth 1 40

- JANNETTAZ (EDWARD).** A Guide to the Determination of Rocks: being an Introduction to Lithology. Translated from the French by G. W. Plympton, Professor of Physical Science at Brooklyn Polytechnic Institute. 12mo, cloth..... 1 50
- JOHNSTON, Prof. J. F. W., and CAMERON, Sir CHAS.** Elements of Agricultural Chemistry and Geology. Seventeenth edition. 12mo, cloth..... 2 60
- JOYNSON (F. H.).** The Metals used in Construction. Iron, Steel, Bessemer Metal, etc. Illustrated. 12mo, cloth 75
- Designing and Construction of Machine Gearing. Illustrated. 8vo, cloth.. 2 00
- KANSAS CITY BRIDGE (THE.)** With an Account of the Regimen of the Missouri River and a Description of the Methods used for Founding in that River. By O. Chanute, Chief Engineer, and George Morrison, Assistant Engineer. Illustrated with 5 lithographic views and 12 plates of plans. 4to, cloth... 6 00
- KAPP (GISBERT C. E.).** Electric Transmission of Energy and its Transformation, Subdivision, and Distribution. A Practical Hand-book. Fourth edition, revised. 12mo, cloth..... 3 50
- Dynamos, Alternators and Transformers. 138 Illustrations. 12mo, cloth..... 4 00
- KEMPE (H. R.).** The Electrical Engineer's Pocket-Book of Modern Rules, Formulæ, Tables and Data. Illustrated. 32mo, mor. gilt..... 1 75
- KENNELLY (A. E.).** Theoretical Elements of Electro Dynamic Machinery. 8vo, cloth..... 1 50
- KILGOUR, M. H., SWAN, H., and BIGGS, C. H. W.** Electrical Distribution; its Theory and Practice. 174 Illustrations. 12mo, cloth..... 4 00
- KING (W. H.).** Lessons and Practical Notes on Steam. The Steam Engine, Propellers, etc., for Young Marine Engineers, Students, and others. Revised by Chief Engineer J. W. King, United States Navy. Nineteenth edition, enlarged. 8vo, cloth ... 2 00
- KINGDON (J. A.).** Applied Magnetism. An introduction to the Design of Electromagnetic Apparatus. 8vo, cloth..... 3 00

- KIRKALDY (WM. G.).** Illustrations of David Kirkaldy's System of Mechanical Testing, as Originated and Carried On by him during a Quarter of a Century. Comprising a Large Selection of Tabulated Results, showing the Strength and other Properties of Materials used in Construction, with explanatory Text and Historical Sketch. Numerous engravings and 25 lithographed plates. 4to, cloth..... 20 00
- KIRKWOOD (JAS. P.).** Report on the Filtration of River Waters for the supply of Cities, as practised in Europe, made to the Board of Water Commissioners of the City of St. Louis. Illustrated by 30 double-plate engravings. 4to, cloth..... 7 50
- LARRABEE (C. S.).** Cipher and Secret Letter and Telegraphic Code, with Hog's Improvements. The most perfect Secret Code ever invented or discovered. Impossible to read without the key. 18mo, cloth 60
- LAZELLE (H. M.).** One Law in Nature. A New Corpuscular Theory comprehending Unity of Force, Identity of Matter, and its Multiple Atom Constitution, etc. 12mo, cloth..... 1 50
- LEASK (A. RITCHIE).** Breakdowns at Sea and How to Repair Them. With eighty-nine Illustrations. 8vo, cloth. Second edition..... 2 00
- Triple and Quadruple Expansion Engines and Boilers and their Management. With fifty-nine illustrations. Third edition, revised. 12mo, cloth.. 2 00
- Refrigerating Machinery: Its Principles and Management. With sixty-four illustrations. 12mo, cloth 2 00
- LECKY (S. T. S.).** "Wrinkles" in Practical Navigation. With 130 illustrations. 8vo, cloth. Ninth edition, revised..... 8 40
- LEVY (C. L.).** Electric Light Primer. A Simple and Comprehensive Digest of all of the most important facts connected with the running of the dynamo, and electric lights, with precautions for safety. For the use of persons whose duty it is to look after the plant. 8vo, paper..... 50

- LIVACHE (ACH., Ingenieur Civil Des Mines).** The Manufacture of Varnishes, Oil Crushing, Refining and Boiling and Kindred Industries. Translated from the French and greatly extended, by John Geddes McIntosh. 8vo, cloth. Illustrated.....net 5 00
- LOCKE (ALFRED G., and CHARLES G.)** A Practical Treatise on the Manufacture of Sulphuric Acid. With 77 Constructive Plates drawn to scale Measurements, and other Illustrations. Royal 8vo, cloth. 10 00
- LOCKERT (LOUIS).** Petroleum Motor-Cars. 12mo, cloth 1 50
- LOCKWOOD (THOS. D.).** Electricity, Magnetism, and Electro-Telegraphy. A Practical Guide for Students, Operators, and Inspectors. 8vo, cloth. Third edition... 2 50
- Electrical Measurement and the Galvanometer; its Construction and Uses. Second edition. 32 illustrations. 12mo, cloth.... 1 50
- LODGE (OLIVER J.).** Elementary Mechanics, including Hydrostatics and Pneumatics. Revised edition. 12mo, cloth..... 1 50
- LORING (A. E.).** A Hand-book of the Electro-Magnetic Telegraph. Paper boards..... 50
Cloth. 75
Morocco..... 1 00
- LUCE (Com. S. B.).** Text-Book of Seamanship. The Equipping and Handling of Vessels under Sail or Steam. For the use of the U. S. Naval Academy. Revised and enlarged edition, by Lt. Wm. S. Benson. 8vo, cloth.....10 00
- LUNGE (GEO.).** A Theoretical and Practical Treatise on the Manufacture of Sulphuric Acid and Alkali with the Collateral Branches. Vol. I. Sulphuric Acid, Second edition, revised and enlarged. 342 illustrations. 8vo, cloth.....15 00
Vol. II. Second edition, revised and enlarged. 8vo, cloth.....16 80
Vol III. 8vo, cloth. New edition, 1896.....15 00
- LUNGE. (GEO.), and HURTER, F.** The Alkali Maker's Pocket-Book. Tables and Analytical Methods for Manufacturers of Sulphuric Acid, Nitric Acid, Soda, Potash and Ammonia. Second edition. 12mo, cloth 3 00

- LUQUER (LEA McILVAINE, Ph. D.).** Minerals in Rock Sections. The Practical Method of Identifying Minerals in Rock Sections with the microscope, Especially arranged for Students in Technical and Scientific Schools. 8vo. cloth. Illustrated. net 1 50
- MACCORD (Prof. C. W.).** A Practical Treatise on the Slide-Valve by Eccentrics, examining by methods the action of the Eccentric upon the Slide-Valve, and explaining the practical processes of laying out the movements, adapting the Valve for its various duties in the Steam Engine. Second edition. Illustrated. 4to, cloth. 2 50
- MAGUIRE (Capt. EDWARD. U. S. A.).** The Attack and Defence of Coast Fortifications. With Maps and Numerous Illustrations. 8vo, cloth. 2 50
- MAGUIRE (WM. R.).** Domestic Sanitary Drainage and Plumbing Lectures on Practical Sanitation. 332 illustrations. 8vo. 4 00
- MARKS (EDWARD C. R.).** Mechanical Engineering Materials: their Properties and Treatment in Construction. 12mo, cloth. Illustrated. 60
- Notes on the Construction of Cranes and Lifting Machinery. 12mo, cloth. 1 00
- MARKS (G. C.).** Hydraulic Machinery Employed in the Concentration and Transmission of Power. 12mo, cloth. 1 25
- MAVER (WM.).** American Telegraphy: Systems. Apparatus, Operation. 450 illustrations. 8vo, cloth. 3 50
- MAYER (Prof. A. M.).** Lecture Notes on Physics. 8vo, cloth. 2 00
- McCULLOCH (Prof. R. S.).** Elementary Treatise on the Mechanical Theory of Heat, and its application to Air and Steam Engines. 8vo, cloth. 3 50
- McNEILL (BEDFORD).** McNeill's Code. Arranged to meet the requirements of Mining, Metallurgical and Civil Engineers, Directors of Mining, Smelting and other Companies, Bankers, Stock and Share Brokers, Solicitors, Accountants, Financiers, and General Merchants. Safety and Secrecy. 8vo, cloth. 6 00

- MERRILL (Col. WM. E., U. S. A.).** Iron Truss Bridges for Railroads. The method of calculating strains in Trusses, with a careful comparison of the most prominent Trusses, in reference to economy in combination, &c. Illustrated. 4to, cloth. Fourth Edition 5 00
- METAL TURNING.** By a Foreman Pattern Maker. Illustrated with 81 engravings. 12mo, cloth..... 1 50
- MINIFIE (WM.).** Mechanical Drawing. A Text-book of Geometrical Drawing for the use of Mechanics and Schools, in which the Definitions and Rules of Geometry are familiarly explained; the Practical Problems are arranged from the most simple to the more complex, and in their description technicalities are avoided as much as possible. With illustrations for Drawing Plans, Sections, and Elevations of Railways and Machinery; an Introduction to Isometrical Drawing, and an Essay on Linear Perspective and Shadows. Illustrated with over 200 diagrams engraved on steel. Ninth thousand. With an appendix on the Theory and Application of Colors. 8vo, cloth 4 00
- Geometrical Drawing. Abridged from the Octavo edition, for the use of schools. Illustrated with 48 steel plates. Ninth edition. 12mo, cloth.... 2 00
- MODERN METEOROLOGY.** A Series of Six Lectures, delivered under the auspices of the Meteorological Society in 1870. Illustrated. 12mo, cloth . 1 50
- MOREING (C. A.), and NEAL (THOMAS).** Telegraphic Mining Code Alphabetically arranged. Second edition. 8vo, cloth..... 8 40
- MORRIS (E.).** Easy Rules for the Measurement of Earthworks by means of the Prismoidal Formula. 8vo, cloth. Illustrated..... 1 50
- MOSES (ALFRED J.), and PARSONS, C. L.** Elements of Mineralogy, Crystallography and Blowpipe Analysis from a practical standpoint. Second thousand. 8vo, cloth. 366 illustrations..... net 2 00
- MOSES (ALFRED J.).** The Characters of Crystals. An Introduction to Physical Crystallography, containing 321 Illustrations and Diagrams. 8vo, 211 pp..... net 2 00

- MCCELLER (F. C. G.).** Krupp's Steel Works. With 88 illustrations. By Felix Schmidt and Montan. Authorized Translation from the German. 4to, cloth.....(In Press.)
- MULLIN (JOSEPH P., M. E.).** Modern Moulding and Pattern-Making. A Practical Treatise upon Pattern Shop and Foundry Work; embracing the Moulding of Pulleys, Spur Gears, Worm Gears, Balance-Wheels, Stationary Engine and Locomotive Cylinders, Globe Valves, Tool Work, Mining Machinery, Screw Propellers, Pattern-Shop Machinery, and the latest improvements in English and American Cupolas; together with a large collection of original and carefully selected Rules and Tables for everyday use in the Drawing Office, Pattern-Shop and Foundry. 12mo, cloth. Illustrated..... 2 50
- MUNRO (JOHN C. E.), and JAMIESON ANDREW C. E.** A Pocket-book of Electrical Rules and Tables for the use of Electricians and Engineers. Thirteenth edition, revised and enlarged. With numerous diagrams. Pocket size. Leather.. 2 50
- MURPHY (J. G., M. E.).** Practical Mining. A Field Manual for Mining Engineers. With Hints for Investors in Mining Properties. 16mo, morocco tucks 1 00
- NAQUET (A.).** Legal Chemistry. A Guide to the Detection of Poisons, Falsification of Writings, Adulteration of Alimentary and Pharmaceutical Substances, Analysis of Ashes, and examination of Hair, Coins, Arms, and Stains, as applied to Chemical Jurisprudence. Translated from the French, by J. P. Battershall, Ph D., with a preface by C. F. Chandler, Ph. D., M. D., LL. D. 12mo, cloth..... 2 00
- NASMITH (JOSEPH).** The Student's Cotton Spinning. Third edition, revised and enlarged. 8vo, cloth. 622 pages. 250 Illustrations..... 3 00
- NEWALL (JOHN W.).** Plain Practical Directions for Drawing, Sizing and Cutting Bevel-Gears, showing how the Teeth may be cut in a Plain Milling Machine or Gear Cutter so as to give them a correct shape from end to end; and showing how to get out all particulars for the Workshop without making any Drawings. Including a Full Set of Tables of Reference. Folding plates. 8vo, cloth..... 1 50

- NEWCOMB (EDWARD W.).** Stepping Stones to Photography. 12mo, cloth. Illustrated. N. Y., 1899. (In Press.)
- NEWLANDS (JAMES).** The Carpenters' and Joiners' Assistant: being a Comprehensive Treatise on the Selection, Preparation and Strength of Materials, and the Mechanical Principles of Framing. Illustrated. Folio, half morocco..... 15 00
- NIPHER (FRANCIS E., A. M.).** Theory of Magnetic Measurements, with an appendix on the Method of Least Squares. 12mo, cloth 1 00
- NOAD (HENRY M.).** The Students' Text-Book of Electricity. A new edition, carefully revised. With an Introduction and additional chapters by W. H. Preece. With 471 illustrations. 12mo, cloth..... 4 00
- NUGENT (E.).** Treatise on Optics; or, Light and Sight theoretically and practically treated. with the application to Fine Art and Industrial Pursuits. With 103 illustrations. 12mo, cloth. 1 50
- O'CONNOR (HENRY).** The Gas Engineer's Pocket Book. Comprising Tables, Notes and Memoranda; relating to the Manufacture, Distribution and Use of Coal Gas and the Construction of Gas Works. 12mo, full leather, gilt edges.... 3 50
- LOUDIN (M. A.).** Standard Polyphase Apparatus and Systems. Fully illustrated 3 00
- PAGE (DAVID).** The Earth's Crust, A Handy Outline of Geology. 16mo, cloth..... 75
- PALAZ (A., ScD.).** A Treatise on Industrial Photometry, with special application to Electric Lighting Authorized translation from the French, by George W. Patterson, Jr. Second edition, revised. 8vo, cloth. Illustrated..... 4 00
- PARSHALL (H. F.), and HOBART H. M.** Armature Windings of Electric Machines. With 140 full page plates, 65 tables, and 165 pages of descriptive letter-press. 4to, cloth..... 7 50
- PARSHALL (H. F.), and EVAN PARRY.** Electrical Equipment of Tramways.....(In Press.)
- PEIRCE (B.).** System of Analytic Mechanics. 4to, cloth .. 10 00
- Linear Associative Algebra. New edition, with addenda and notes, by C. L. Pierce. 4to, cloth 4 00

- PERRINE (F. A. C., A. M., D. Sc.).** Conductors for Electrical Distribution; their Manufacture and Materials, the Calculation of Circuits, Pole Line Construction, Underground Working and other Uses. (In Press.)
- PERRY (JOHN).** Applied Mechanics. A Treatise for the use of students who have time to work experimental, numerical and graphical exercises illustrating the subject. 8vo, cloth. 650 pages., net 2 50
- PHILLIPS (JOSHUA).** Engineering Chemistry. A Practical Treatise for the use of Analytical Chemists, Engineers, Iron Masters, Iron Founders, students and others. Comprising methods of Analysis and Valuation of the principal materials used in Engineering works, with numerous Analyses, Examples and Suggestions. 314 illustrations. Second edition, revised and enlarged. 8vo, cloth..... 4 00
- PICKWORTH (CHAS. N.).** The Indicator Handbook. A Practical Manual for Engineers. Part I. The Indicator: Its Construction and Application. 81 illustrations. 12mo, cloth..... 1 50
- The Slide Rule. A Practical Manual of Instruction for all Users of the Modern Type of Slide Rule, exhibiting the Application of the Instrument to the Everyday Work of the Engineer,—Civil, Mechanical and Electrical. 12mo, flexible cloth. Fifth edition. 80
- PLANE TABLE (THE).** Its Uses in Topographical Surveying. From the Papers of the United States Coast Survey. Illustrated. 8vo, cloth..... 2 00
- PLANTE (GASTON).** The Storage of Electrical Energy, and Researches in the Effects created by Currents, combining Quantity with High Tension. Translated from the French by Paul B. Elwell. 89 illustrations. 8vo..... 4 00
- PLATTNER.** Manual of Qualitative and Quantitative Analysis with the Blow-Pipe. From the last German edition, revised and enlarged, by Prof. Th. Richter, of the Royal Saxon Mining Academy. Translated by Prof. H. B. Cornwall, assisted by John H. Caswell. Illustrated with 87 wood-cuts and one lithographic plate. Seventh edition, revised. 560 pages. 8vo, cloth..... 5 00

- PLYMPTON (Prof. GEO. W.).** The Blow Pipe. A Guide to its use in the Determination of Salts and Minerals. Compiled from various sources. 12mo, cloth 1 50
- The Aneroid Barometer: its Construction and Use. Compiled from several sources. Fourth edition. 16mo, boards. Illustrated... .. 50
Morocco..... 1 00
- POCKET LOGARITHMS,** to Four Places of Decimals, including Logarithms of Numbers, and Logarithmic Sines and Tangents to Single Minutes. To which is added a Table of Natural Sines, Tangents, and Co-Tangents. 16mo, boards.... 50
- POPE (F. L.).** Modern Practice of the Electric Telegraph. A Technical Hand-book for Electricians, Managers and Operators. Fifteenth edition, rewritten and enlarged, and fully illustrated. 8vo, cloth. 1 50
- POPPELWELL (W. C.).** Elementary Treatise on Heat and Heat Engines. Special y adapted for engineers and students of engineering. 12mo, cloth. Illustrated..... 3 00
- POWLES (H. H.).** Steam Boilers.....(In Press.)
- PRAY (Jr., THOMAS).** Twenty Years with the Indicator; being a Practical Text-Book for the Engineer or the Student, with no complex Formulæ. Illustrated. 8vo, cloth..... 2 50
- Steam Tables and Engine Constant. Compiled from Regnault, Rankine and Dixon directly, making use of the exact records. 8vo, cloth..... 2 00
- PRACTICAL IRON FOUNDING.** By the Author of "Pattern Making," &c, &c. Illustrated with over one hundred engravings. 12mo, cloth..... 1 50
- PREECE (W. H.).** Electric Lamps(In Press.)
- PREECE (W. H.), and STUBBS, A. T.** Manual of Telephony. Illustrations and plates. 12mo, cloth. 4 50
- PREMIER CODE.** (See Hawk, Wm. H.)
- PRESCOTT (Prof. A. B.).** Organic Analysis. A Manual of the Descriptive and Analytical Chemistry of certain Carbon Compounds in Common Use: a Guide in the Qualitative and Quantitative Analysis of Organic Materials in Commercial and Pharma-

- ceutical Assays, in the estimation of Impurities under Authorized Standards, and in Forensic Examinations for Poisons, with Directions for Elementary Organic Analysis. Fourth edition. 8vo, cloth..... 5 00
- PRESCOTT (Prof. A. B.).** Outlines of Proximate Organic Analysis, for the Identification, Separation, and Quantitative Determination of the more commonly occurring Organic Compounds. Fourth edition. 12mo, cloth 1 75
- First Book in Qualitative Chemistry. Eighth edition. 12mo, cloth 1 50
- and Otis Coe Johnson. Qualitative Chemical Analysis. A Guide in the Practical Study of Chemistry and in the work of Analysis. Fourth fully revised edition. With Descriptive Chemistry extended throughout..... 3 50
- PRITCHARD (O. G.).** The Manufacture of Electric Light Carbons. Illustrated. 8vo, paper 60
- PULLEN (W. W. F.).** Application of Graphic Methods to the Design of Structures. Specially prepared for the use of Engineers. 12mo, cloth. Illustrated. net 2 50
- PULSIFER (W. H.).** Notes for a History of Lead. 8vo, cloth, gilt tops..... 4 00
- PYNCHON (Prof. T. R.).** Introduction to Chemical Physics, designed for the use of Academies, Colleges, and High Schools. Illustrated with numerous engravings, and containing copious experiments with directions for preparing them. New edition, revised and enlarged, and illustrated by 269 illustrations on wood. 8vo, cloth..... 3 00
- RADFORD (Lieut. CYRUS S.).** Hand-book on Naval Gunnery. Prepared by Authority of the Navy Department. For the use of U. S. Navy, U. S. Marine Corps and U. S. Naval Reserves. Revised and enlarged, with the assistance of Stokely Morgan, Lieut. U. S. N. Third edition. 12mo, flexible leather. 2 00
- RAFTER (GEO. W.), and M. N. BAKER.** Sewage Disposal in the United States. Illustrations and folding plates. Second edition. 8vo, cloth..... 6 00
- RAM (GILBERT S.).** The Incandescent Lamp and its Manufacture. 8vo, cloth.. 3 00

THE VAN NOSTRAND SCIENCE SERIES.

- No. 60.—STRENGTH OF WROUGHT-IRON BRIDGE MEMBERS. By S. W. Robinson, C.E.
- No. 61.—POTABLE WATER AND METHODS OF DETECTING IMPURITIES. By M. N. Baker.
- No. 62.—THE THEORY OF THE GAS-ENGINE. By Dougald Clerk. Second edition. With additional matter. Edited by F. E. Idell, M.E.
- No. 63.—HOUSE DRAINAGE AND SANITARY PLUMBING. By W. P. Gerhard. Sixth edition. Revised.
- No. 64.—ELECTRO-MAGNETS. By Th. du Moncel. 2d revised edition.
- No. 65.—POCKET LOGARITHMS TO FOUR PLACES OF DECIMALS.
- No. 66.—DYNAMO-ELECTRIC MACHINERY. By S. P. Thompson. With notes by F. L. Pope. Third edition.
- No. 67.—HYDRAULIC TABLES BASED ON "KUTTER'S FORMULA." By P. J. Flynn.
- No. 68.—STEAM-HEATING. By Robert Briggs. Third edition, revised, with additions by A. R. Wolff.
- No. 69.—CHEMICAL PROBLEMS. By Prof. J. C. Foye. Third edition, revised and enlarged.
- No. 70.—EXPLOSIVE MATERIALS. By M. Bertholet.
- No. 71.—DYNAMIC ELECTRICITY. By John Hopkinson, J. A. Schoolbred, and R. E. Day.
- No. 72.—TOPOGRAPHICAL SURVEYING. By George J. Specht, Prof. A. S. Hardy, John B. McMaster, and H. F. Walling.
- No. 73.—SYMBOLIC ALGEBRA; OR, THE ALGEBRA OF ALGEBRAIC NUMBERS. By Prof. W. Cain.
- No. 74.—TESTING MACHINES: THEIR HISTORY, CONSTRUCTION, AND USE. By Arthur V. Abbott.
- No. 75.—RECENT PROGRESS IN DYNAMO-ELECTRIC MACHINES. Being a Supplement to Dynamo-Electric Machinery. By Prof. Sylvanus P. Thompson.
- No. 76.—MODERN REPRODUCTIVE GRAPHIC PROCESSES. By Lieut. James S. Pettit, U.S.A.
- No. 77.—STADIA SURVEYING. The Theory of Stadia Measurements. By Arthur Winslow.
- No. 78.—THE STEAM-ENGINE INDICATOR, AND ITS USE. By W. B. Le Van.
- No. 79.—THE FIGURE OF THE EARTH. By Frank C. Roberts, C.E.
- No. 80.—HEALTHY FOUNDATIONS FOR HOUSES. By Glenn Brown.

JUN 25 1907

THE VAN NOSTRAND SCIENCE SERIES.

- No. 81.--WATER METERS: COMPARATIVE TESTS OF ACCURACY, DELIVERY, ETC. Distinctive features of the Worthington, Kennedy, Siemens, and Hesse meters. By Ross E. Browne.
- No. 82.--THE PRESERVATION OF TIMBER BY THE USE OF ANTISEPTICS. By Samuel Bagster Boulton, C. E.
- No. 83.--MECHANICAL INTEGRATORS. By Prof. Henry S. H. SHAW, C. E.
- No. 84.--FLOW OF WATER IN OPEN CHANNELS, PIPES, CONDUITS, SEWERS, ETC. With Tables. By P. J. Flynn, C. E.
- No. 85.--THE LUMINIFEROUS ÆTHER. By Prof. de Volson Wood.
- No. 86.--HAND-BOOK OF MINERALOGY: DETERMINATION AND DESCRIPTION OF MINERALS FOUND IN THE UNITED STATES. By Prof. J. C. Foye. Fourth edition, revised.
- No. 87.--TREATISE ON THE THEORY OF THE CONSTRUCTION OF HELICOIDAL OBLIQUE ARCHES. By John L. Culley, C. E.
- No. 88.--BEAMS AND GIRDERS. Practical Formulas for their Resistance. By P. H. Philbrick.
- No. 89.--MODERN GUN COTTON: ITS MANUFACTURE, PROPERTIES, AND ANALYSIS. By Lieut. John P. Wisser, U. S. A.
- No. 90.--ROTARY MOTION AS APPLIED TO THE GYROSCOPE. By Gen. J. G. Barnard.
- No. 91.--LEVELING: BAROMETRIC TRIGONOMETRIC AND SPIRIT. By Prof. I. O. Baker.
- No. 92.--PETROLEUM: ITS PRODUCTION AND USE. By Boverton Redwood, F. I. C., F. C. S.
- No. 93.--RECENT PRACTICE IN THE SANITARY DRAINAGE OF BUILDINGS. With Memoranda on the Cost of Plumbing Work. Second edition, revised. By William Paul Gerhard, C. E.
- No. 94.--THE TREATMENT OF SEWAGE. By Dr. C. Meymott Tidy.
- No. 95.--PLATE GIRDER CONSTRUCTION. By Isami Hiroi, C. E. 2d edition, revised and enlarged.
- No. 96.--ALTERNATE CURRENT MACHINERY. By Gisbert Kapp, Assoc. M. Inst., C. E.
- No. 97.--THE DISPOSAL OF HOUSEHOLD WASTES. By W. Paul Gerhard, Sanitary Engineer.
- No. 98.--PRACTICAL DYNAMO BUILDING FOR AMATEURS. HOW TO WIND FOR ANY OUTPUT. By Frederick Walker. Fully illustrated.
- No. 99.--TRIPLE - EXPANSION ENGINES AND ENGINE TRIALS. By Prof. Osborne Reynolds. Edited, with notes, etc., by F. E. Idell, M. E.

THE VAN NOSTRAND SCIENCE SERIES.

- No. 100.—HOW TO BECOME AN ENGINEER, or the Theoretical and Practical Training necessary in fitting for the duties of the Civil Engineer. By Prof. Geo. W. Plympton.
- No. 101.—THE SEXTANT, and other Reflecting Mathematical Instruments. With Practical Hints for their adjustment and use. By F. R. Brainard, U. S. Navy.
- No. 102.—THE GALVANIC CIRCUIT INVESTIGATED MATHEMATICALLY. By Dr. G. S. Ohm, Berlin, 1827. Translated by William Francis. With Preface and Notes by the Editor, Thomas D. Lockwood, M.I.E.E.
- No. 103.—THE MICROSCOPICAL EXAMINATION OF POTABLE WATER. With Diagrams. By Geo. W. Rafter.
- No. 104.—VAN NOSTRAND'S TABLE BOOK FOR CIVIL AND MECHANICAL ENGINEERS. Compiled by Prof. Geo. W. Plympton.
- No. 105.—DETERMINANTS. An Introduction to the Study of, with Examples and Applications. By Prof. G. A. Miller.
- No. 106.—COMPRESSED AIR. Experiments upon the Transmission of Power by Compressed Air in Paris. (Popp's System.) By Prof. A. B. W. Kennedy. The Transmission and Distribution of Power from Central Stations by Compressed Air. By Prof. W. C. Unwin.
- No. 107.—A GRAPHICAL METHOD FOR SWING-BRIDGES. A Rational and Easy Graphical Analysis of the Stresses in Ordinary Swing-Bridges. With an Introduction on the General Theory of Graphical Statics. By Benjamin F. La Rue. 4 Plates.
- No. 108.—SLIDE VALVE DIAGRAMS. A French Method for Constructing Slide Valve Diagrams. By Lloyd Bankson, B.S., Assistant Naval Constructor, U. S. Navy. 8 Folding Plates.
- No. 109.—THE MEASUREMENT OF ELECTRIC CURRENTS. Electrical Measuring Instruments. By James Swinburne. Meters for Electrical Energy. By C. H. Wordingham. Edited, with Preface, by T. Commerford Martin. Folding Plate and numerous illustrations.
- No. 110.—TRANSITION CURVES. A Field-Book for Engineers, containing Rules and Tables for Laying out Transition Curves. By Walter G. Fox, C.E.
- No. 111.—GAS-LIGHTING AND GAS-FITTING. Specifications and Rules for Gas-Piping. Notes on the advantages of Gas for Cooking and Heating, and Useful Hints to Gas Consumers. Second edition, rewritten and enlarged. By Wm. Paul Gerhard, C. E.
- No. 112.—A PRIMER ON THE CALCULUS. By E. Sherman Gould, M. Am. Soc. C. E.

TEXT**Colleges and Techn**

0 033 261 069 7

THEORETICAL

With an Introduction to the Calculus. Designed as a Text-Book for Technical Schools and Colleges, and for the use of Engineers, Architects, &c. By JULIUS WEISSBACH, Ph. D. Translated from the German by EDWARD F. COOPER, A. M., Mining Engineer. One Volume, 8vo, 1112 pages, 902 Illustrations. Cloth, \$6.00. Sheep, \$7.50.

The Graphical Statics of Mechanisms.

A Guide for the use of Machinists, Architects and Engineers; and also a Text-Book for Technical Schools. By GUSTAV HERMANN, Professor in the Royal Polytechnic School at Aix-la-Chapelle. Translated and abridged by A. P. SMITH, M. E. Fourth Ed. 12mo, cloth, illustrated.

Elementary Mechanism.

Text-Book for Students of Mechanical Engineering. By ARTHUR F. WOODS, Assistant Engineer U. S. Navy, Assistant Professor of Mechanical Engineering, Johns Hopkins State University, etc., and ALBERT W. STARK, M. E., Assistant Engineer U. S. Navy, Professor of Mechanical Engineering, Purdue University, Lafayette, Ind. Fourth Edition. 12mo, cloth, illustrated.

Elements of Mechanics.

Including Kinematics, Statics and Dynamics. With applications. By Professor T. W. WRIGHT, of Cornell University. Third edition, revised. 8vo, cloth, illustrated.

Bowser's Analytic Mechanics.

An Elementary Treatise on Analytic Mechanics. With numerous examples. By EDW. A. BOWSER, M. E. 12th Edition. 12mo, cloth.

Elementary Mechanics, including Hydrostatics and Pneumatics.

By Professor OLIVER J. LODGE. Revised Edition. 12mo, cloth, illustrated.

Applied Mechanics.

A Treatise for the Use of Students who have done the Work Experimental, Numerical, and Graphical. Illustrating the Subject. By JOHN H. COOPER, M. E., F. R. S. 8vo, cloth.